

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400389857

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 100322

4. Contact Name: Julie Webb

2. Name of Operator: NOBLE ENERGY INC

Phone: (720) 587-2316

3. Address: 1625 BROADWAY STE 2200

Fax:

City: DENVER State: CO Zip: 80202

5. API Number 05-123-15373-00

6. County: WELD

7. Well Name: KUGEL W

Well Number: 4-4

8. Location: QtrQtr: NWNW Section: 4 Township: 2N Range: 66W Meridian: 6

Footage at surface: Distance: 660 feet Direction: FNL Distance: 660 feet Direction: FWL

As Drilled Latitude: As Drilled Longitude:

GPS Data:

Data of Measurement: PDOP Reading: GPS Instrument Operator's Name:

** If directional footage at Top of Prod. Zone Dist.: feet. Direction: Dist.: feet. Direction:

Sec: Twp: Rng:

** If directional footage at Bottom Hole Dist.: feet. Direction: Dist.: feet. Direction:

Sec: Twp: Rng:

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 11/20/1991 13. Date TD: 11/26/1991 14. Date Casing Set or D&A: 11/27/1991

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7548 TVD** 17 Plug Back Total Depth MD 7472 TVD**

18. Elevations GR 4896 KB 4906

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

Gamma Ray CCL/CBL

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24	0	613	310	0	613	CALC
1ST	7+7/8	2+7/8	6.5	0	7,529	300	6,500	7,548	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: 10/16/2012

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom
	S.C. 1.1		308	0	885

Details of work:

Control well w/ 2% KCL water. PU w/ blade bit, scraper, 237 jts. Tagged fill at 7449'KB. Roll hole clean. TIH w/ RBP, retrieved head, 230 jts tubing. Set RBP @ 7219' KB w/ 230 jts. Unland casing. Pick up mule shoe and TIH w/136 jts of 1 1/4" to 4273'. Established circulation and roll hole clean. Test iron to 2500 psi. Pump 3bbls spacer. Pump 308 sks of "G" neat 15.8 ppg cement from 885' to surface. Reland Casing at 35K. Bond log from 1000' to surface. Tagged sand plug at 7221'KB. Circulate and roll clean. RIH w/ retrieving head and establish circulation and latch onto RBP. Roll hole clean and release RBP. Land 1 1/4" 2.33# J-55 tubing to 7338.95'. Rig down and move off.

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
			<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

Gamma Ray CCL/CBL hard copies will be mailed.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Julie Webb

Title: Regulatory Analyst

Date: _____

Email: juliewebb@nobleenergyinc.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400389886	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Directional Survey **	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>

General Comments**User Group** **Comment****Comment Date**

--	--	--

Total: 0 comment(s)