

## US ROCKIES REGION

## Anadarko Daily Summary Report

Well: PLATTE 20-35

Project: COLORADO-WELD

Site: PLATTE 9-35 PAD

Rig Name No: ECWS 22/22, SES 3/3

Event: WELL WORK EXPENSE

Start Date: 1/29/2013

End Date: 2/13/2013

Spud Date: 10/17/2003

Active Datum: RKB @4,761.99usft (above Mean Sea Level)

UWI: 0/4/N/67/W/35/0/SESE/6/0/S/-1230/E/0/1300/0/0

Report No	Report Date	MD (usft)	24 Hr Summary
1	01/29/2013		SLICK LINE TAG AT 7289' ROAD RIG AND HAUL EQUIP TO LOC MIRU ECWS #22 SPOT EQUIP WAIT ON PUMP AND TANK WAIT ON COMPANION FLANGE TBG/CSG=110 PSI SCP=45 PSIG CONTROL WELL NDWH NUBOP UNLAND PROD CSG SECURE WELL SDFN
2	01/30/2013		CREW TO LOC MIRU EMI CREW TOO H (NO BAD TBG FOUND) PU RBP TIH SET AT 3815' ROLL HOLE TEST CSG TO 2000# GPPD TEST SPOT SAND ON RBP TOO H W/ TBG NDBOP NDWH UNLAND PROD CSG NU DUAL ENTRY EQUIP NUBOP TIH W/ 20 JNTS 1-1/4" TO 685' SECURE WELL SDFN
3	01/31/2013		CREW TO LOC BLEW DOWN SC=45 PSI TIH W/ 1-1/4" WORK STRING INTO OPEN HOLE TO 3709' CIRCULATE OPEN HOLE UNTIL RETURNS CLEANED UP LOAD OPEN HOLE V DRILLING MUD 9.6# 40 VISC SECURE WELL SDFN
4	02/01/2013		CREW TO LOC CIRCULATE WELL W/ DRILLING MUD UNTIL BJ ARRIVED MIRU BJ PUM 700 SK ANNULAR FILL TOO H W/ 1-1/4" WORK STRING NDBOP AND DUAL ENTRY EQUIP RELAND PROD CSG AT 65000# NU NEW 5000# WELL HEAD NUBOP SECURE WELL SDFN
5	02/04/2013		CREW TO LOC MIRU E-LINE RUN CBL FROM 3750'-500' TOC=870' RD E-LINE PU RETRIEVING HEAD TIH TAG SAND CIRCULATE SAND OFF RBP RELEASE TOO H PU NCSN TIH LAND PROD TBG W/ 233 JNTS @ 7184.94' BROACH TO SN NDBOP NUWH SWI RDMO
100	02/06/2013		MIRU SES rig #3 TP 0 CP 120 SC 0 IFL 5900'. Broached tbg. Swabbed 8 bbl water. SI. FFL 5800' gassy TP blow CP 180 SDFN
101	02/07/2013		Crew travel TP 200 CP 290 IFL 5700'. Blew tbg down. Swabbed 8 bbl, CP built to 320#, well kicked off and flowed to gas. SI. FFL 3800' gassy TP 200 CP 240 RDMO SES rig #3
102	02/13/2013		TIME ON: 11:55, ROUTE: N21, WINS: 75538, PROJECT TYPE: WWE, PROD: NB-CD, TP: 500, CP: 500, CHOKE: 32 AT SEP, BATT #: 34001942, GATHERER: KMG, STAT #: _046508, LINE #: 16-58-4, COMMENTS: RWTP UP TBG AFTER BRADENHEAD REPAIR.