

US ROCKIES REGION

Anadarko Daily Summary Report

Well: HSR-VAN PORTFLIET 6-10A

Project: COLORADO-WELD

Site: HSR-VAN PORTFLIET 6-10A

Rig Name No: ECWS 21/21

Event: CONST- CAP WELL WORK

Start Date: 11/9/2012

End Date:

Spud Date: 2/5/2000

Active Datum: RKB @4,868.99usft (above Mean Sea Level)

UWI: 0/2/N/65/W/10/0/NWSE/6/0/N/501/W/0/-2130/0/0

Report No	Report Date	MD (usft)	24 Hr Summary
1	12/03/2012		MIRU ECWS # 21. SCP 0.RU PUMP AND TANK. SPOT IN TBG TRAILER. RU CABLE INC. FISH PLUNGER, TAG FILL @ 7862'. SWI, SDFN.
2	12/04/2012		BLOW WELL DOWN, CONTROL WELL W/ 50 BBLS. NDNU, RU PRS AND EMI TBG ON TOO. FOUND 178 GOOD JTS AND 70 BAD JTS. TIH W/ CSG SCRAPER, 2-3/8" TBG AND NEW REPLACEMENT TBG TO 7612'. TOO. W/ 100 JTS. SWI, SDFN.
3	12/05/2012		FINISH TOO. W/ SCRAPER. TIH W/ BULLDOG BAILER. TAG @ 7862', BAIL WELL CLEAN TO PB @ 7887'. TOO. AND LD BAILER. RU WARRIOR WIRELINE, RIH AND SET CIBP @ 7540'. DUMP BAIL 2 SX SAND ON PLUG. LOAD AND TEST CSG TO 2500#, HELD GOOD. SEE REMARKS
4	12/06/2012		RU HYDROTESTER, TIH AND SET CIBP @ 6892'. LOAD AND TEST CSG TO 500. RU BAKER HUGHES, PUMP 10 BBLS MUDCLEAN, 10 BBLS H2O, THEN MIX AND PUMP 100 SX OF 50/50 POZ W/ 3% GEL, .1% SMS, 20% SILICA FLOUR AND .4% FL-52 MIXED @ 13.5 PPG. SEE REMARKS
5	12/07/2012		RU WARRIOR WIRELINE, RIH W/ CBL TOOLS. TAG @ 6642', LOG W/ GOOD CMT TO 6352'. RD WIRELINE. TIH W/ 3-7/8" ROCK BIT AND 2-3/8" PRODUCTION TBG. BROACH TBG TO SN, NDNU AND LAND WELL @ 6527.40' W/ 208 JTS. SWI, RDMO.