

US ROCKIES REGION

Anadarko Daily Summary Report

Well: FT ST VRRAIN 1

| | | |
|--|------------------------|-------------------------|
| Project: COLORADO-WELD | Site: FT ST VRRAIN 1 | Rig Name No: ECWS 22/22 |
| Event: WELL WORK EXPENSE | Start Date: 10/10/2012 | End Date: |
| Active Datum: RKB @4,789.99usft (above Mean Sea Level) | | Spud Date: 3/30/1981 |
| UWI: 0/3/N/67/W/3/0/SENE/6/0/0/0/0/0/0 | | |

| Report No | Report Date | MD (usft) | 24 Hr Summary |
|-----------|-------------|-----------|--|
| 1 | 10/10/2012 | | MIRU SLICKLINE PULL PLUNGER AND NOGO AT 7510' TAG FILL AT 7596' MIRU ECWS #22 TBG/CSG=200 PSIG SCP=100 PSIG BLEW DOWN TBG AND CSG CONTROL WELL W/ 20 BBLs DWN TBG 20 BBLs DOWN CSG NDWH NUBOP SECURE WELL SDFN |
| 2 | 10/11/2012 | | CREW TO LOC TBG/CSG=50 SCP=100 MIRU EMI TOO H W/ TBG FOUND 18 BAD OUT OF 238 JNTS PU BAILER TIH BAIL FILL TO PBD TOO H LD TOOLS PU RBP AND PKR TIH SET RBP AT 6710' ROLL GAS FROM HOLE SET PKR TEST RBP AND CSG TO 2000# GOOD TEST (SEE REMARKS) |
| 3 | 10/12/2012 | | CREW TO LOC TBG/CSG=0 SCP=50 TALLEY AND TIH W/ 1-1/4" TBG TO 4463' HAD TO CIRCULATE DOWN IN IN A FEW SPOTS CONDITION HOLE FOR 3 HRS PUMP 190 BBLs DRILLING MUD W/ RIG PUMP MIRU BJ TEST LINES PUMP ANNULAR CEMENT OVER SUSSEX (SEE REMARKS) |
| 4 | 10/13/2012 | | CREW TO LOC SCP=0 MIRU E-LINE RIH LOG FROM 4700'-4000' TOC=4130 ENGINEER LOOKED AT LOG DECIDED TO PUMP CMENT OVER SUSSEX AGAIN THEN SURFACE JOB, TIH W/ 1-1/4" TBG TO 4104' ROLL HOLE W/ DRILLING MUD MIRU BJ SERVICES (SEE REMARKS) |
| 5 | 10/14/2012 | | CREW TO LOC MIRU E-LINE LOAD CSG RIH LOG FROM 4650'-3750' AND 1000'-260' ENGINEER APPROVED CEMENT TIH W/ RETRIEVING HEAD ROLL SAND OFF RBP LATCH ONTO AND RELEASE TOO H LD TOOLS PU NCSN TIH LAND PROD (SEE REMARKS) |