

**FORM  
5**Rev  
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
Document Number:  400392579			
Date Received:			

**DRILLING COMPLETION REPORT**

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 100185	4. Contact Name: Marina Ayala
2. Name of Operator: ENCANA OIL & GAS (USA) INC	Phone: (720) 876-5905
3. Address: 370 17TH ST STE 1700	Fax: (720) 876-6905
City: DENVER State: CO Zip: 80202-	

5. API Number 05-045-20805-00	6. County: GARFIELD
7. Well Name: DW	Well Number: 8616C-28 P28496
8. Location: QtrQtr: SESE Section: 28 Township: 4S Range: 96W Meridian: 6	
Footage at surface: Distance: 656 feet Direction: FSL	Distance: 453 feet Direction: FEL
As Drilled Latitude: 39.667859	As Drilled Longitude: -108.165746

## GPS Data:

Data of Measurement: 01/12/2012 PDOP Reading: 4.2 GPS Instrument Operator's Name: Brandon Birdsall

\*\* If directional footage at Top of Prod. Zone Dist.: 758 feet. Direction: FSL Dist.: 1286 feet. Direction: FEL

Sec: 28 Twp: 4S Rng: 96W

\*\* If directional footage at Bottom Hole Dist.: 727 feet. Direction: FSL Dist.: 1353 feet. Direction: FEL

Sec: 28 Twp: 4S Rng: 96W

9. Field Name: WILDCAT	10. Field Number: 99999
11. Federal, Indian or State Lease Number: COC65555	

12. Spud Date: (when the 1st bit hit the dirt) 12/31/2011	13. Date TD: 02/24/2012	14. Date Casing Set or D&A: 02/24/2012
---	-------------------------	--

## 15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 10983 TVD** 10925	17 Plug Back Total Depth MD 10927 TVD** 10869
--------------------------------------	---

18. Elevations GR 7791 KB 7813	One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.
--------------------------------	--

## 19. List Electric Logs Run:

CBL and Mud.

## 20. Casing, Liner and Cement:

**CASING**

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	30	20	53	0	118	160	22	118	CALC
SURF	14+3/4	9+5/8	36	0	2,098	717	22	2,098	CALC
1ST	8+3/4	4+1/2	11.6	0	10,949	1,730	3,353	10,983	CBL

**STAGE/TOP OUT/REMEDIAL CEMENT**

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

**FORMATION LOG INTERVALS AND TEST ZONES**

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WILLIAMS FORK	6,979	10,818	<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	10,819	10,983	<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Marina Ayala

Title: Permitting Technician

Date: \_\_\_\_\_

Email: marina.ayala@encana.com

**Attachment Check List**

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400392597	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400392589	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400392586	PDF-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400392587	LAS-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400392590	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

**General Comments****User Group****Comment****Comment Date**

--	--	--

Total: 0 comment(s)