



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7289 • FAX (970) 353-7712

OUR INVOICE

601125

Date	10/17/12	Well Owner	Kerr McGee	Well No.	15A-31HZ	Lease	Nichols
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (major #42)						
City, State Zip	Denver, Colorado 80202						
Type of Job			Depth	Ft. 920			
Surface	9 5/8" CSG 36" 13 1/2" Hole		Bottom of Surface	Ft. 915			
Plug			Plug Landed @	873	Ft.	Time On	0300
Production			Pipe Landed @	915	Ft.	Plug Down	0600

Description	Qty.	Mess.	Unit Price	Amount
Set Up Charge	1			
Cement Neat	TYPE III	680	SKS	
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge	96	Miles		
Fuel Surcharge	96	miles		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	0458 0504	
Disp. Rate	5 BPM	Mixing	0504 0544	
Slurry Vol.	1.32 ³ Cu.Ft./Sk	Change Valves	0544 0547	
Slurry Wt.	14.8 - 15.0 PPG	Displacement	0547 0600	
Water/Cement	6.25 Gal/SK			
Water Temp.	58°F			
Total Slurry Vol.	159.8	BBLS Cement		
Landed Plug @	825	PSI/Final Lift @	325	PSI
Pre-Flush Wt	30	BBLS H ₂ O		
Displace Wt	67.4	BBLS H ₂ O		
Circulate	5	BBLS Cement		

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		32			
1216/1217		Bulk Truck		32/32		2069368	

800/2090

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim, Adam, Josh A, Tucker

Received By Randy Lake
Customer or His Agent