



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 338220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600376

Date <b>10/13/12</b>	Well Owner <b>Kerr McGee</b>	Well No. <b>37C-31#2</b>	Lessee <b>Nichols</b>
County <b>Weld</b>	State <b>Colorado</b>		
Charge to <b>Kerr McGee Oil &amp; Gas Onshore, LP</b>			
Address <b>1999 Broadway, Suite 3700 (MAJOR 44)</b>			
City, State Zip <b>Denver, Colorado 80202</b>			
Type of Job	Depth	FL <b>940</b>	
Surface <b>9 5/8" CSG-36" 13 1/2" hde</b>	Bottom of Surface	FL <b>932</b>	
Plug	Plug Landed @ <b>886</b>	FL	Time On <b>1150</b>
Production	Pipe Landed @ <b>932</b>	FL	Plug Down <b>1500</b>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <b>✓ Type III</b>	690	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	96	Miles		
Fuel Surcharge	96	Miles		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	1407	1413	
Disp. Rate 5 BPM	Mixing	1413	1443	
Slurry Vol. 1.32 <sup>3</sup> Cu.Ft./Sk	Change Valves	1443	1446	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	1446	1500	
Water/Cement 6.25 Gal/SK				
Water Temp. <b>59°F</b>				
Total Slurry Vol. <b>162.2</b>	BBLs Cement			<b>20692.84</b>
Landed Plug @ <b>750</b>	PSI/Final Lift @ <b>400</b>	PSI		<b>80012050</b>
Pre-Flush Wt <b>30</b>	BBLs H <sub>2</sub> O	Tax Reference Code	Sub Total	
Displace Wt <b>68.4</b>	BBLs H <sub>2</sub> O	State - CO 2.9%	Tax	
Circulate <b>5</b>	BBLs Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<b>1308</b>		Pump Truck		<b>32</b>			
<b>1314/1317</b>		Bulk Truck		<b>32/32</b>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By

**Justin Ewan's Steve**

Received By

**Eric R**  
Customer or His Agent