



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7290 • FAX (970) 353-7712

OUR INVOICE

## 601074

Date <u>10/1/12</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>44-3842</u>	Lease <u>Miles</u>				
County <u>Weld</u>	State <u>Colorado</u>						
Charge to <u>Kerr McGee Oil &amp; Gas Onshore, LP</u>							
Address <u>1999 Broadway, Suite 3700 (MOTOR 44)</u>							
City, State Zip <u>Denver, Colorado 80202</u>							
Type of Job	Depth	Fl. <u>925</u>					
Surface <u>9 5/8" 156-36" 13 1/2" Hole</u>	Bottom of Surface	Fl. <u>918</u>					
Plug	Plug Landed @ <u>875</u>	Fl. Time On <u>0445</u>					
Production	Pipe Landed @ <u>918</u>	Fl. Plug Down <u>0745</u>					
Description	Qty.	Meas.	Unit Price	Amount			
Set Up Charge	1						
Cement Nest <u>✓ Type III</u>	<u>1080</u>	SKS					
Proz. Mix							
Calcium Chloride	2.5	%					
Gel % Flo-Crete 1/4 # Per Sack							
Mileage Charge	<u>130</u>	Miles					
Fuel Surcharge	<u>130</u>	Miles					
Additional Cement		SKS					
Mixing Rate	4 BPM	Pre-Flush	<u>0653-0659</u>				
Disp. Rate	5 BPM	Mixing	<u>0659-0729</u>				
Slurry Vol.	1.32' Cu.Ft./Sk	Change Valves	<u>0729-0730</u>				
Slurry Wt.	14.8 - 15.0 PPG	Displacement	<u>0730-0745</u>				
Water/Cement	6.25 Gal/SK						
Water Temp.	<u>160° F</u>						
Total Slurry Vol.	<u>159.8</u>	BBLS Cement					
Landed Plug @	<u>700</u>	PSI/Final Lift @ <u>300</u>	PSI				
Pre-Flush W/ <u>30</u>	BBLS H <sub>2</sub> O	Tax Reference Code	Sub Total				
Displace W/ <u>107.66</u>	BBLS H <sub>2</sub> O	State <u>CO 2.9%</u>	Tax				
Circulate <u>5</u>	BBLS Cement		Total				
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>44</u>			
<u>1214/1218</u>		Bulk Truck		<u>44/44</u>			<u>2057.553</u>

80012090

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin Ryan - Steve

Received By Randy Case  
Customer or His Agent