

## US ROCKIES REGION

## Anadarko Daily Summary Report

Well: UPRR 22 PAN AM "O" #1

Project: COLORADO-WELD

Site: UPRR 22 PAN AM "O" #1

Rig Name No: BASIC 1549/1549

Event: ABANDONMENT

Start Date: 2/4/2013

End Date: 3/4/2013

Spud Date: 11/14/1974

Active Datum: RKB @4,912.99usft (above Mean Sea Level)

UWI: 0/3/N/66/W/29/0/NESW/6/0/0/0/0/0/0

Report No	Report Date	MD (usft)	24 Hr Summary
1	02/04/2013		RU Cable & pull bumper spring. Tag dill @ 7879;. RD Cable. MIRU Basic 1549.
2	02/05/2013		Kill well. NU BOP. TOO H & tally tbq. RU Warrior & set CIBP @ 7750'. Dump bail 2 sks cmt on CIBP. Run CBL from 7700' to 6870'. Cmt top @ 7198'. Test csg to 1000 psi. Pumped into @ 1000 psi @ 1 bpm. %00 spi on Shut down. Shoot 3 (.62") (see remarks)
3	02/06/2013		PU stinger & TIH. Wait on mud tank. RU Baker & pump 200 sks G cmt to cover Niobrara. Spot 30 bbls mud to btm of tbq. TOO H. SI. SDFN.
4	02/07/2013		RU Warrior. Shoot squeeze holes @ 5300' & 4120' w/3 .62" holes @ each depth. Set retainer @ 4130'. PU stinger & TIH. RU Sanjel & cmt Shannon & Sussex w/700 sks G cmt. Sting out. Circ well w/drlg mud. TOO H.
5	02/08/2013		RU Warrior & jet cut csg @ 880'. ND BOP. Unset csg slips. NU BOP to surface head. LD 4 1/2" csg. TIH w/tbg to 975'. RU Baker & set surface plug w/250 sks Type III cmt w/2% CaCl2. LD tbq. TIH to 93'. Ciec for 3 hrs. PU tbq to tag cmt @ 170'. LD tbq. SI. SD
6	02/09/2013		ND BOP. RU Warrior & set 8 5/8" CIBP @ 150'. NU BOP. Test CIBP to 1000 psi. OK. ND BOP. RDMO.
7	03/04/2013		Crew travel, safety. Dug up surface casing. Cut casing 6' below GL, removed WH. Tagged @ 155'. Filled w 94 bags 5000# cement. Capped casing w plate containing well info. Backfilled.
8	03/04/2013		TIME : 10:00, ROUTE : N31, WINS: 74956, PROJECT TYPE: P&A, BATT#: 34002526, GATHERER: KMG, STATION: OO8075, LINE : 16-177-4, COMMENTS: P&A'D OFFLINE - WELLBORE IS PERMANENTLY ABANDONED