

FORM  
2

Rev  
12/05

# State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400349566

Date Received:

## APPLICATION FOR PERMIT TO:

1.  Drill,  Deepen,  Re-enter,  Recomplete and Operate

### 2. TYPE OF WELL

OIL  GAS  COALBED  OTHER \_\_\_\_\_  
SINGLE ZONE  MULTIPLE  COMMINGLE

Refiling   
Sidetrack

PluggingBond SuretyID

20030009

3. Name of Operator: NOBLE ENERGY INC 4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200  
City: DENVER State: CO Zip: 80202

6. Contact Name: JAN KAJIWARA Phone: (303)228-4092 Fax: (303)228-4286  
Email: jkajiwara@nobleenergyinc.com

7. Well Name: NCLP PC AA Well Number: 04-68-1HN

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 16231

## WELL LOCATION INFORMATION

10. QtrQtr: NWNW Sec: 4 Twp: 6N Rng: 63W Meridian: 6  
Latitude: 40.521090 Longitude: -104.450320

Footage at Surface: 698 feet FNL/FSL FNL 250 feet FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4711 13. County: WELD

### 14. GPS Data:

Date of Measurement: 06/21/2012 PDOP Reading: 1.6 Instrument Operator's Name: Adam Kelly

15. If well is  Directional  Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1125 FNL 899 FWL 899 FEL/FWL 1125 FNL 535 FEL 535  
Bottom Hole: FNL/FSL 1125 FNL 535 FEL/FWL 535 FEL 535  
Sec: 4 Twp: 6N Rng: 63W Sec: 4 Twp: 6N Rng: 63W

16. Is location in a high density area? (Rule 603b)?  Yes  No

17. Distance to the nearest building, public road, above ground utility or railroad: 668 ft

18. Distance to nearest property line: 698 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 100 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		640	GWA

21. Mineral Ownership:  Fee  State  Federal  Indian Lease #: \_\_\_\_\_

22. Surface Ownership:  Fee  State  Federal  Indian

23. Is the Surface Owner also the Mineral Owner?  Yes  No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease?  Yes  No

23b. If 23 is No:  Surface Owners Agreement Attached or  \$25,000 Blanket Surface Bond  \$2,000 Surface Bond  \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T6N-R63W Sec 4: W/2, less and except a tract of land being a part of lot 3. Wellbore will produce from multiple leases. Horizontal well crosses lease line within GWA horizontal wellbore unit; distance to lease line is 0 feet; distance to nearest unit boundary is 535 feet.

25. Distance to Nearest Mineral Lease Line: 0 ft 26. Total Acres in Lease: 288

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated?  Yes  No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling?  Yes  No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling?  Yes  No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)?  Yes  No

31. Mud disposal:  Offsite  Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method:  Land Farming  Land Spreading  Disposal Facility Other: CLOSED LOOP

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	18+1/2	16		0	100	6	100	0
SURF	13+3/4	9+5/8	36	0	550	270	550	0
1ST	8+3/4	7	26	0	7,057	480	7,057	
1ST LINER	6+1/8	4+1/2	11.6	6907	16,231			

32. BOP Equipment Type:  Annular Preventer  Double Ram  Rotating Head  None

33. Comments 1ST STRING TOP OF CEMENT = 200' ABOVE NIOBRARA. TWO WELL PAD NCLP PC AA04-68-1HN AND AA04-69-1HN. GOING TO NCLP PC AA04 ECONODE 400349554. COMPLETION WATER TO BE STAGED ON NCLP PC AA04-64-1HN PAD. SEE ATTACHED SAVAGE & SAVAGE REPORT-BURROWING OWLS NESTING IN PRAIRIE DOG COLONY SURROUNDING WELLSITE. NO OCCUPANCY 3/15 TO 10/31 WITHIN 150' OF BURROW. NEAREST WELL IS NCLP PC AA04-19 (API: 05-123-29481) 100' S. Unit Configuration = Sec 3: N/2, Sec 4: N/2. Noble Energy Inc. requests approval of Rule 318A.a Surface location outside window; 318A.c Twinning location exception, request letter and signed waiver are attached. Noble Energy Inc. requests approval of a Rule 318.A.m. exception location; wellhead lateral is to be located less than 150' from an existing wellbore. A Wildlife Assessment report is included in this permit package, as the well location is in a sensitive wildlife area.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan?  Yes  No

36. Is this application part of submitted Oil and Gas Location Assessment?  Yes  No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: JAN KAJIWARA

Title: REGULATORY ANALYST Date: \_\_\_\_\_ Email: jkajiwara@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

API NUMBER

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

### Attachment Check List

Att Doc Num	Name
400362078	30 DAY NOTICE LETTER
400362079	EXCEPTION LOC WAIVERS
400362080	WELL LOCATION PLAT
400362081	SENSITIVE AREA DATA
400387970	EXCEPTION LOC REQUEST
400387971	EXCEPTION LOC REQUEST
400387973	PROPOSED SPACING UNIT
400387974	DEVIATED DRILLING PLAN
400387978	DIRECTIONAL DATA
400390758	OFFSET WELL EVALUATION

Total Attach: 10 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

### BMP

<u>Type</u>	<u>Comment</u>
Material Handling and Spill Prevention	Spill prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with Oil & Gas operations throughout the state of Colorado in accordance with CFR 112.
Storm Water/Erosion Control	Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with Oil & Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE) General Permit No. COR-038637. BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. BMP's used will vary according to the location, and will remain in place until the pad reaches final reclamation.
General Housekeeping	Housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur prompt cleanup is required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each work day. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pickup trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.

Total: 3 comment(s)