

PDC Energy  
 Johnson 2  
 SWNW 19 5N 63W  
 Weld County, CO  
 Current Wellbore - NOT TO SCALE!!!  
 3/27/2013

API#: 05-123-14191

GL Elevation: 4559'

Surface Casing:
8 5/8" 24# @ 300' W/ 220 sks cmt.

First String
3 1/2" 9.1# @ 6656' w/ 310 sks cmt

Second String
0

Parkman

Top of Cement:
5890'

Perforations	
Old:	Codell: 6604'-6619'
	0
	0
	0
New:	0
	0
	0
	0

CIBP @ 6560'
--------------

--

Codell
--------

PBTD:	6700'
Casing TD:	0

#### NOTES

CIBP @ 6560' w/ 2 sx cement on top, holes in csg from 2434'-3371'