

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400358811

Date Received:

02/28/2013

PluggingBond SuretyID

20080034

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: BAYSWATER EXPLORATION AND PRODUCTION LLC

4. COGCC Operator Number: 10261

5. Address: 730 17TH ST STE 610

City: DENVER State: CO Zip: 80202

6. Contact Name: Jennifer Angel-Lear Phone: (303)407-1282 Fax: (720)536-3440
Email: jangellear@petro-fs.com

7. Well Name: Triangle Well Number: 32-22

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7889

WELL LOCATION INFORMATION

10. QtrQtr: SENW Sec: 22 Twp: 7N Rng: 65W Meridian: 6

Latitude: 40.561813 Longitude: -104.650423

Footage at Surface: 1800 feet FNL/FSL 2345 feet FEL/FWL
FNL FWL

11. Field Name: Wyatt School Field Number: 95200

12. Ground Elevation: 4832 13. County: WELD

14. GPS Data:

Date of Measurement: 09/19/2012 PDOP Reading: 1.3 Instrument Operator's Name: Brian Ritz

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
2141 FNL 75 FWL 2141 FNL 75 FWL
Sec: 22 Twp: 7N Rng: 65W Sec: 22 Twp: 7N Rng: 65W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 350 ft

18. Distance to nearest property line: 183 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 2000 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL		160	GWA
GREENORN	GRNHN		160	GWA
NIOBRARA	NBRR		160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20100112

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

The mineral Lease description is the W/2 of Sec. 22, T7N, R65W containing 320 acres.

25. Distance to Nearest Mineral Lease Line: 75 ft 26. Total Acres in Lease: 320

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	600	420	600	0
1ST	7+7/8	4+1/4	11.6	0	7,889	896	7,889	3,500

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments No conductor casing will be set. The closest PR well is the Triangle 18-22 . The unit configuration is the SE of the NW of Sec. 22. T7N,R65W. The Exception Loc. Waiver for COGCC RULE 318Aa and COGCC Rule 318Ac is attached. The mineral Lease description is the W/2 of Sec. 22 T7N R65W containing 320 acresThe proposed spacing unit is SENE, NESE of Sec. 21 T7N,65W and SWNW, NWSW of Sec. 22 T7N, R65W.The surface owner is KSJJ, LLCThe mineral owner is TriangleCross Ranch

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Jennifer Angel-Lear

Title: Regulatory Technician Date: 2/28/2013 Email: jangellear@petro-fs.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Date retrieval failed for the subreport 'IntPolicy_NTO' located at: W:\eetpub\Net\Reports\policy_nto.rdl. Please check th

Attachment Check List

Att Doc Num	Name
400361716	30 DAY NOTICE LETTER
400361729	DIRECTIONAL DATA
400361736	DEVIATED DRILLING PLAN
400361740	PLAT
400383239	EXCEPTION LOC REQUEST
400384247	EXCEPTION LOC WAIVERS
400395902	EXCEPTION LOC REQUEST
400395925	PROPOSED SPACING UNIT

Total Attach: 8 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Planning	When feasible develop multiple well sites by using directional drilling to reduce cumulative impacts and adverse impacts on wildlife resources.
Drilling/Completion Operations	When available and reasonable use a closed-loop drilling mud system to preclude the use of an earthen reserve pits when available. Light Sources will likewise be directed downwards, and away from occupied structures where possible. Once the drilling and completions rigs leave the site, there will be no permanently installed lighting on site. The operator will work with the Town of Severance to develop a traffic plan for access to the locations and traffic through Town streets.
Site Specific	Fence the well site after drilling to restrict public and wildlife access. Keep well site location, the road, and the pipeline easement free of noxious weeds, litter and debris. Spray for noxious weeds, and implement dust control, as needed. Operator will not permit the release or discharge of any toxic or hazardous chemicals or wastes on Owner's Land. Construct and maintain gates where any roads used by operator, its employees, or contractors cross through fences on the leased premises.
Storm Water/Erosion Control	Use water bars, and other measures to prevent erosion and non-source pollution. Implement and maintain BMPs to control stormwater runoff in a manner that minimizes erosion, transport of sediment offsite, and site degradation. Co-locate gas and water gathering lines whenever feasible, and mitigate any erosion problems that arise due to the construction of any pipeline(s).
Construction	Remove only the minimum amount of vegetation necessary for the construction of roads and facilities. Conserve topsoil during excavation and reuse as cover on disturbed areas to facilitate regrowth of vegetation. No construction or routine maintenance activities will be performed during periods when the soil is too wet to adequately support construction equipment.
Interim Reclamation	Utilize only such area around each producing well as is reasonably necessary. Restore the remainder of the well site location to its original condition within a reasonable time after the completion of operations. All reseeding shall be done with grasses consistent with the Rocky Mountain native mix or other grasses reasonably requested by surface owner and during planting period suggested by Owner.
Final Reclamation	All surface restoration shall be accomplished to the satisfaction of Owner. All reseeding shall be done with grasses consistent with the Rocky Mountain native mix or other grasses reasonably requested by surface owner and during planting period suggested by Owner. Final reclamation shall be completed to the reasonable satisfaction of the Owner as soon as practical after installation (weather permitting) and in accordance with regulatory agency standards (BLM/COGCC).

Total: 7 comment(s)