

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400397185

Date Received:

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER ☐
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

PluggingBond SuretyID

20040060

3. Name of Operator: BARRETT CORPORATION* BILL

4. COGCC Operator Number: 10071

5. Address: 1099 18TH ST STE 2300

City: DENVER State: CO Zip: 80202

6. Contact Name: Mary Pobuda Phone: (303)312-8511 Fax: (303)291-0420

Email: mpobuda@billbarrettcorp.com

7. Well Name: Pappenheim Well Number: 6-62-23-59H

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 10923

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 23 Twp: 6N Rng: 62W Meridian: 6

Latitude: 40.479610 Longitude: -104.291410

Footage at Surface: 250 feet FNL/FSL 1999 feet FEL/FWL FWL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 4699 13. County: WELD

14. GPS Data:

Date of Measurement: 02/07/2013 PDOP Reading: 1.6 Instrument Operator's Name: Wyatt Hall

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 650 FNL 1750 FEL 650 FSL 1750 FEL 650
Sec: 23 Twp: 6N Rng: 63W Sec: 23 Twp: 6N Rng: 63W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 222 ft

18. Distance to nearest property line: 250 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1285 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR		640	ALL

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #:

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Please see attached lease map.

25. Distance to Nearest Mineral Lease Line: 1750 ft

26. Total Acres in Lease: 3720

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☒ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	20	16	65	0	60	50	60	0
SURF	13+1/2	9+5/8	36	0	800	430	800	0
1ST	8+3/4	7	26	0	6,966	580	6,966	600
1ST LINER	6+1/8	4+1/2	11.6	6000	10,923			

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments This well is an exception location. SUA surface description is in meets and bounds, please refer attached surface map labeled "Other". The spacing application for up to eight horizontal wells within a 640-acre drilling and spacing unit consisting of section 23, Township 6 North, Range 62 West, 6th P.M., for the production of oil, gas and associated hydrocarbons from the Niobrara Formation was approved on 3/25/13 (Docket No. 1303-AW-18).

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Mary Pobuda

Title: Permit Analyst Date: _____ Email: mpobuda@billbarrettcorp.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Date retrieval failed for the subreport 'IntPolicy_MTO' located at: W:\testpub\Net\Report\policy_mto.rdl. Please check th

Attachment Check List

Att Doc Num	Name
400397797	DIRECTIONAL DATA
400397798	WELL LOCATION PLAT
400397799	DEVIATED DRILLING PLAN
400397801	LEASE MAP
400397802	SURFACE AGRMT/SURETY
400397803	OTHER
400397804	OFFSET WELL EVALUATION
400397805	EXCEPTION LOC WAIVERS
400397806	EXCEPTION LOC REQUEST

Total Attach: 9 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)