

US ROCKIES REGION

Anadarko Daily Summary Report

Well: RADEMACHER THEO J UT #1

Project: COLORADO-WELD

Site: RADEMACHER THEO J UT #1

Rig Name No: BASIC 1549/1549

Event: ABANDONMENT

Start Date: 2/14/2013

End Date: 3/16/2013

Spud Date: 7/31/1973

Active Datum: RKB @4,871.99usft (above Mean Sea Level)

UWI: SW/NE/0/3/N/67/W/30/0/0/6/0/N/1,650.00/0/0/0/0/0

Report No	Report Date	MD (usft)	24 Hr Summary
1	02/14/2013		RU Frontier. Run Gyro from 7500' to surface. Pull 2 plungers. Could not pull bumper spring. RD Frontier.
2	02/15/2013		MIRU Basic 1549. Kill well. ND well head. NU BOP. TOO H & tally tbg. SI. SDFN.
3	02/16/2013		RU Warrior & run 3.75" gauge ring to 7600'. Run CIBP & set @ 7550'. Dump bail 2 sks cmt on CIBP. Run CBL from 7484' to 6400'. Cmt top @ 6840'. Shoot 3 - .62" holes @ 6800'. Run retainer & stacked @ 6218'. Set retainer @ 6210'. PU stinger & test in hole SI
4	02/19/2013		Finish TIH & space out tbg. RU Baker & cmt above Niobrara w/250 sks cmt. Sting out. Circ drlg mud. TOO H. RU Warrior & cut off csg @ 4850'. Circ well with drlg mud to remove gas trapped in mud. SI. SDFN.
5	02/20/2013		Circ well with drlg mud to kill. Could not get well to die. RU Warrior & set retainer @ 3860'. PU stinger & TIH. SI. SDFN.
6	02/21/2013		Wait on Baker. RU Baker & set plug across Shannon & Sussex W;930 sks G cmt. LD tbg. RU Warrior & cut csg @ 540'. The well started to blow. Circ well to kill. SI. SDFN.
7	02/22/2013		Circ csg to kill well. ND BOP. Pull csg from slips. NU BOP to surface head. LD csg. SI. SDFN.
8	02/23/2013		Open well & let die. TIH w/tbg tpo 590'. RU Baker. Set surface plug w/250 sks Type III cmt w/2% CaCl2. LD tbg. SI. SDFN.
9	02/25/2013		Wait on stuck crude trk. Thaw well head. RU Warrior & tag cmt @ 225'. Btm of surface @ 231'. RD Warrior. Wait on cmt. TIH to 225'. RU Sanjel & set 25 sk plug from 225' to 125'. LD tbg. SI. SDFN.
10	02/26/2013		PU tbg to tag cmt top @ 160'.. ND BOP. RU Warrior & set 8 5/8" CIBP @ 100' GL. RDMO Basic 1549.
11	03/16/2013		Crew travel. Safety. Dug up surface casing. Cut casing 7' below GL. Tagged @ 28'. Filled casing w 16 bags 5000# cement. Capped casing with plate containing well info. Backfilled.
12	03/16/2013		TIME ON: 13:0, ROUTE: S24, WINS: 74661, PROJECT TYPE: P&A, PROD: JSND, TP: N/A, CP: N/A, CHOKE: N/A, BATT #: 34003744, GATHERER: KMG, STAT #: 045505, LINE #: 20-448-3, COMMENTS: P&A'd OFFLINE.