



Well Name: WPX Energy RMT.
Well Name: RGU 332-24-198
Pad Name: RGU 31-24-198
Legal Description: NWSESEC24TWP1SRNG98W
Unit: Ryan Gulch
Unit # COC068239X
COGCC # 96850
API # 05-103-11808
County: Rio Blanco
Field: Sulphur Creek
Field # 80090
Rig Name and Number: CYCLONE 29
Williams Supervisor: Ted Ragsdale
Phone number at rig: 970-988-3854

RECEIVED
 MAR 21 2013
COGCC

This notice, sent on
 ran and cemented
 Depth casing landed
 Volume pumped
 Sack of cement used
 Cement density
 Yield cubic ft/sack
 Stages
 Lift Pressure
 Bumped plug
 Bump pressure
 Floats held
 Returns
 Losses

| |
|---------------------|
| 3/21/2013 |
| 4-1/2" Production |
| 12,787' |
| 314.6, 136.1, 229.1 |
| 640, 400, 735 |
| 11.0, 12.7, 13.5 |
| 2.76, 1.91, 1.75 |
| SINGLE |
| 2700 |
| YES |
| 3237 |
| YES |
| FULL /LOST |
| 480 |

is to inform you that Williams casing.

psi
psi

Additionally:

LOST RETURNS WHILE PUMPING LEAD CEMENT W/ 50 BBLS REMAINING & NEVER REGAINED RETURNS, LIFT PRESSURE BUILT T/ 2700 PSI , RECIPRICATING CASING AS LONG AS ABLE, LOST 480 BBLS MUD, BUMPED BLUG @ 4 BBLS MIN. @ 3237 PSI , CHECKED FLOATS & FLOATS HELD, SET SLIPS ON CASING W/ 110K

*Also, SEE FORM 42 # 400394359,
 LOST ARC DURING CMT
 D.A.*