

WELL LOCATION CERTIFICATE

SECTION 21, TOWNSHIP 7 NORTH, RANGE 66 WEST, 6TH P.M.

NW CRN SEC. 21
3.25" AC LS 10855

N88°47'53"E

2662.8'

N1/4 CRN SEC. 21
2.5" AC LS 9644

N88°48'28"E

2662.8'

NE CRN SEC. 21
3.25" AC LS 10855

2656.9'

N00°35'27"W

NOTES:

THIS IS A HORIZONTAL DRILL WELL.
BOTTOM HOLE AT 500' FSL, 640' FEL.
WELL FALLS IN A WHEAT FIELD.
SEE LOCATION DRAWING FOR IMPROVEMENTS

W1/4 CRN SEC. 21
2.5" AC LS 16154

2657.0'

N00°35'39"W

GROUND ELEVATION = 4970'

LAT. & LONG. = N 40.56686°
W 104.77916°

SW CRN SEC. 21
3.25" AC LS 7242

S89°09'43"W

S1/4 CRN SEC. 21
3.25" AC LS 26595

2669.4'

BH = 500' FSL,
640' FEL.
LAT. & LONG. = N 40.55456°
W 104.77574°

S89°09'39"W

2669.4'

SE CRN SEC. 21
3.25" AC LS 26595

2673.4'
S00°43'54"E
BASIS OF BEARINGS

E1/4 CRN SEC. 21
3.25" AC LS 26595


2673.8'

S00°44'36"E

I HEREBY STATE TO PDC ENERGY THAT THE SURFACE LOCATION FOR THE WELL
THORNTON 21U-443 IS LOCATED 350' FNL & 1570' FEL, SEC. 21, T7N, R66W, 6PM

LEGEND

- FOUND MONUMENT
- PROPOSED WELL
- BOTTOM HOLE



SCALE 1" = 1000'

ELEVATION SOURCE = USGS 7.5' QUAD.MAP CONTOURS
NGVD 1929 DATUM.

LAT. & LONG. ARE DIFFERENTIALLY CORRECTED (WGS'84)
USING (DGPS) WITH (PDOP) VALUE OF 1.7.

THOMAS G. CARLSON, PLS 24657
HORSESHOE SURVEYING, LLC

SHOWN DISTANCES ARE FIELD MEASURED - EXTERIOR SECTION LINES
ARE DRAWN TO SCALE (BEST APPROX. OR FOUND MONUMENT).

THIS IS NOT A MONUMENTED BOUNDARY SURVEY, IT IS ONLY A
DRAWING INTENDED TO DEPICT THE WELL LOCATION TO SECTION LINES.

DISTANCES TO WELL SHOWN PERPENDICULAR
TO SECTION LINES.

PREPARED BY:

HORSESHOE SURVEYING, LLC
PO BOX 150458
LAKEWOOD, CO 80215
(720)872-0196

WELL NAME:

THORNTON 21U-443

LOCATION:

WELD COUNTY, CO
NE1/4, SEC. 21, T7N, R66W, 6TH P.M.

DRAWING DATE:

10-13-12

FIELD DATE:

10-11-12

BY:

TGC

CHKD:

JOB NO.

SHEET NO.

1 OF 1