



CEMENTER'S WELL SERVICE, INC.
 P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

900015

Date	3/11/13	Well Owner	BONANZA CREEK	Well No.	31-34-16 HUB	Lease	State Pronghorn
County	Weld	State	COLORADO				
Charge to	BONANZA CREEK ENERGY, INC.						
Address	410 17TH ST., SUITE 1500 (E. 103160-128)						
City, State, Zip	DENVER, COLORADO 80202						
Type of Job			Depth	Ft. 466			
Surface	9 5/8" CSB-36# 13 1/2" Hole		Bottom of Surface	Ft. 456			
Plug			Plug Landed @	412	Ft.	Time On	2000
Production			Pipe Landed @	456	Ft.	Plug Down	2300

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat	380	SKS		
Poz. Mix				
Calcium Chloride	3.0	%		
Gel				
Mileage Charge	196	Miles		
Fuel Surcharge	196	Miles		
Additional Cement		SKS		
Mixing Rate	4 BPM	Centralizers	5	
Disp. Rate	5 BPM	Cement Guide Shoe	1	
Slurry Vol.	1.18 Cu.Ft./Sk	Cement Basket		
Slurry Wt.	15.0-15.2 PPG	Baffle Plate	1	
Water/Cement	5.0 Gal/Sk	Box Thread Lock	1	
Water Temp.	50°F			
Total Slurry Vol.	79.8	BBLs Cement		
Landed Plug @	600	PSI/Final Lift @ 300	PSI	
Pre-Flush W/	15	BBLs H ₂ O	Tax Reference Code	Sub Total
Displace W/	31.8	BBLs H ₂ O	State	CO 2.9%
Circulate	4	BBLs Cement		Total

Approved For Payment
 AFE# 13059 Cost Center CO601093
 Company# Acct. Code 8305-108
 Approved By: *Kenneth Smith*

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1208		Pump Truck		98			
1214		Bulk Truck		98			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered by Justin, Steve & Ewan

Received by *Kenneth Smith*

Customer or His Agent