

PDC Energy  
Wiedeman 12-29  
SWNW 29 4N 66W  
Weld County, CO  
Current Wellbore - NOT TO SCALE!!!  
4/11/2013

API#: 05-123-14355

GL Elevation: 4743'

|                                      |
|--------------------------------------|
| Surface Casing:                      |
| 8 5/8" 24# @ 220' W/ 150<br>sks cmt. |

|                                       |
|---------------------------------------|
| First String                          |
| 3 1/2" 9.1# @ 7385' w/ 210<br>sks cmt |

|               |
|---------------|
| Second String |
| 0             |

|         |
|---------|
| Parkman |
|         |

|                |
|----------------|
| Top of Cement: |
| 6632'          |

| Perforations |                     |
|--------------|---------------------|
| Old:         | Codell: 7252'-7266' |
|              | 0                   |
|              | 0                   |
|              | 0                   |
| New:         | 0                   |
|              | 0                   |
|              | 0                   |
|              | 0                   |

|              |
|--------------|
| CIBP @ 7200' |
|--------------|

|  |
|--|
|  |
|--|

|        |
|--------|
| Codell |
|--------|

|            |       |
|------------|-------|
| PBTD:      | 7385' |
| Casing TD: | 0     |

#### NOTES

CIBP @ 7200' w/ 2 sx cement on top, holes in csg from 2278'-2340'