

Kirby Robertson 3-21

13 3/8" 42# @ 160' TOC @ Surface

7" 23# 1381' TOC @ Surface

8 5/8" @ 1090'-2425' TOC @ 1440'

CMT Balance Plug @ 2066'-2286' (220')

4 1/2" 11.6# 2286'-5640' TOC @ 4890'

CMT Balance Plug @ 5518'-5643' (125')

Open Hole @ 5640'-5693'

PBTD @ 2066'

1. MIRU
2. Set Balance Plug @ 1490'-1330'
3. Set 10 sks @ surface
4. Cut off WH
5. Add Cement to annulus if necessary
6. Weld on plate Info
7. RDMO