

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400402960

Date Received:

04/12/2013

PluggingBond SuretyID

20100017

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☒

Sidetrack ☐

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Alexis Bidgood Phone: (720)876-3074 Fax: ()

Email: Alexis.Bidgood@encana.com

7. Well Name: MCU Well Number: 16-13C (M16W)

8. Unit Name (if appl): Middleton Creek Unit Number: COC068997
X

9. Proposed Total Measured Depth: 11033

WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 16 Twp: 7S Rng: 93W Meridian: 6

Latitude: 39.439862 Longitude: -107.783340

Footage at Surface: 543 feet FNL/FSL 1253 feet FEL/FWL FSL

11. Field Name: Mamm Creek Field Number: 52500

12. Ground Elevation: 7887 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 02/04/2013 PDOP Reading: 0.0 Instrument Operator's Name: Ted T. Taggart

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 480 FSL 639 FWL 480 FSL 639 FWL
Bottom Hole: FNL/FSL 480 FSL 639 FWL
Sec: 16 Twp: 7S Rng: 93W Sec: 16 Twp: 7S Rng: 93W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 815 ft

18. Distance to nearest property line: 543 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 330 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES			

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC055604

22. Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T7S-R93W; Sec. 16: W2NE, E2W2, NWNW, SWSW, SE.

25. Distance to Nearest Mineral Lease Line: 640 ft

26. Total Acres in Lease: 480

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	0.25"	0	60	5	60	0
SURF	12+1/4	9+5/8	36	0	1,203	444	1,203	0
1ST	7+7/8	4+1/2	11.6	0	11,033	1,044	11,033	0

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments TOC > 200' above MVRD. A sundry to change BHL, TD, surface and production casing programs was approved on 03/28/2013. Will be a tapered hole. Conductor casing will change from 0'-40' with a 24" hole and 16" casing to 0-60' with a 24" hole and 16" casing size. Surface casing will go from 0-200' with a hole size of 14-3/4" and casing size of 9-5/8". Surface Casing will continue from 200' to 1203' with a hole size of 12-1/4" and casing size of 9-5/8" Cement volume for surface casing will increase from 386 sx to 444 sx. Production casing will change from 0-11399' with a hole size of 7-7/8" and casing size of 4-1/2" to a tapered hole from 0-7953' with hole size of 8-3/4" and casing size of 4-1/2" It will continue on from 7953' and 11033' with a hole size of 7-7/8" and casing size of 4-1/2", thus decreasing the TD from 11399' to 11033'.

34. Location ID: 422418

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Alexis Bidgood

Title: Permitting Analyst

Date: 4/12/2013

Email: Alexis.Bidgood@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05 045 20690 00

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Data retrieval failed for the subreport 'IntPolicy_NTC' located at: W:\Instrub\Net\Reports\policy_ntc.rdl. Please check th

Attachment Check List

Att Doc Num	Name
400402960	FORM 2 SUBMITTED
400403026	DIRECTIONAL DATA
400403397	DEVIATED DRILLING PLAN
400404027	PLAT

Total Attach: 4 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)