



02055752

Well Name: WPX Energy RMT.
Well Name: RGU 314-23-198
Pad Name: RGU 23-23-198
Legal Description: NWNESEC23TWP1SRNG98W
Unit: Ryan Gulch
Unit # COC068239X
COGCC # 96850
API # 05-103-11786
County: Rio Blanco
Field: Sulphur Creek
Field # 80090
Rig Name and Number: CYCLONE 29
Williams Supervisor: Ted Ragsdale.
Phone number at rig: 970-988-3854

RECEIVEDAPR
MAR 15 2013**COGCC**

This notice, sent on	4/14/2013	is to inform you that Williams
ran and cemented	9-5/8" SURFACE	casing.
Depth casing landed	3,844'	
Volume pumped	252.2, 108.2, 368.3	
Sack of cement used	8,003, 101, 055	
Cement density	12.8, 12.8, 12.8	
Yield cubic ft/sack	1.77, 1.96, 1.96	
Stages	2 STAGE	
Lift Pressure	592,480	psi
Bumped plug	YES / YES	
Bump pressure	1,085 , 1,705	psi
Floats held	YES / YES	
Returns	FULL/ LOST/ FULL	
Losses	140	

Additionally:

1ST STAGE W/ 100% EXCESS, HAD FULL RETURNS UNTIL 84
 BBLS GONE ON DISPL, REGAINED @ 154 GONE, WENT T/
 PARTIAL RETURNS LOST 140 BBLS MUD, BUMPED PLUG,
 FLOATS HELD, 1 BBL CONTAMINATED MUD BACK / 2ND
 STAGE PUMPED W/ 70% EXCESS, FULL RETURNS, 140 BBLS
 CEMENT BACK T/ SURFACE BUMPED PLUG/ STAGE TOOL
 CLOSED/ TOPPED OUT FED. RGU 24-23-198 WELL F/ 61' W/ 40
 BBLS 12.8 TAIL, FED. RGU 513-23-198 F/ 78' W/ 50 BBLS & FED.
 RGU 313-23-198 WELL F/ 78' W/ 50 BBLS PUMPED DOWN
 THRU 2" CEMENT LINE TILL CEMENT T/ SURFACE

① 103-11787

② 103-11784

③ 103-11789