



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 9000004

Date	2/2/13	Well Owner	BONANZA CREEK	Well No.	P-T-17 HNB	Lease	Pronghorn
County	Weld	State	COLORADO				
Charge to	BONANZA CREEK ENERGY, INC.						
Address	410 17TH ST., SUITE 1500 (E-5162-128)						
City, State, Zip	DENVER, COLORADO 80202						
Type of Job		Depth		Ft.	453		
Surface	9 5/8" CG-36 # 13 1/2 HOK	Bottom of Surface		Ft.	442		
Plug		Plug Landed @	401	Ft.	Time On	0315	
Production		Pipe Landed @	442	Ft.	Plug Down	1345	

Description		Qty.	Meas.
Set Up Charge		1	
Cement Neat ✓		370	SKS
Stand By Time		3	HRS
Calcium Chloride		3.0	%
Gel % Fio-Cete ¼ # Per Sack			
Mileage Charge		196	Miles
Fuel Surcharge		196	miles
Additional Cement			SKS
Mixing Rate	4 BPM	Centralizers	5
Disp. Rate	5 BPM	Cement Guide Shoe	1
Slurry Vol.	1.18 Cu.Ft./Sk	Cement Basket	
Slurry Wt.	15.0-15.2 PPG	Baffle Plate	1
Water/Cement	5.0 Gal/Sk	Box Thread Lock	1
Water Temp.	48°F		
Total Slurry Vol.	77.7	BBLS Cement	
Landed Plug @	550	PSI/Final Lift @ 250	PSI
Pre-Flush W/ 15	BBLS H <sup>2</sup> O	Tax Reference Code	Sub Total
Displace W/ 30.9	BBLS H <sup>2</sup> O	State	CO 2.9%
Circulate 3	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1208		Pump Truck	AF# 13003	98	Cost Center	COCO1088	
1217		Bulk Truck	Company#	98	Acct. Code	8805-108	

Approved For Payment

Approved By: \_\_\_\_\_

Approved By: \_\_\_\_\_

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered by Justin Steve & Nathan

Received by \_\_\_\_\_

Customer or His Agent