

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400380839

Date Received:

02/22/2013

PluggingBond SuretyID

20100017

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER ☐
SINGLE ZONE ☐ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Bonnie Lamond Phone: (720)876-5156 Fax: (720)876-6177

Email: bonnie.lamond@encana.com

7. Well Name: Hagen Well Number: 15-14C (PC22)

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 7948

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 22 Twp: 7S Rng: 95W Meridian: 6

Latitude: 39.428723 Longitude: -107.986655

Footage at Surface: 561 feet FNL 1728 feet FWL

11. Field Name: Parachute Field Number:

12. Ground Elevation: 6521 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 01/21/2013 PDOP Reading: 0.0 Instrument Operator's Name: Ted T. Taggart

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: 427 FSL 1767 FWL 427 FSL 1767 FWL
Sec: 15 Twp: 7S Rng: 95W Sec: 15 Twp: 7S Rng: 95W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1200

18. Distance to nearest property line: 452 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 360 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	440-62		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #:

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T7S R95W SEC 15: S2SW

25. Distance to Nearest Mineral Lease Line: 427 ft

26. Total Acres in Lease: 80

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	20	.25" wall	0	40	50	40	0
SURF	12+1/4	9+5/8	36	0	964	317	964	0
1ST	7+7/8	4+1/2	11.6	0	7,948	534	7,948	0

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments _____

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Bonnie Lamond

Title: Permitting Technician

Date: 2/22/2013

Email: bonnie.lamond@encana.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 4/20/2013

API NUMBER

05 045 22021 00

Permit Number: _____ Expiration Date: 4/19/2015

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

(1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

(2) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS IS REQUIRED.

(3) EMAIL NOTIFICATION SHALL BE SENT TO COGCC FIELD INSPECTION STAFF, AT THE TIME OF SPUD NOTICE, TO IDENTIFY THE WELL'S LOCATION WITH RESPECT TO BOTH THE SECTOR AND TIER AS DEFINED BY THE RULISON SAMPLING AND ANALYSIS PLAN. EMAIL: Shaun.Kellerby@state.co.us, Mike.Longworth@state.co.us, and Rulison.Submittal@state.co.us

(4) OPERATOR SHALL COMPLY WITH ALL PROVISIONS OF THE MOST RECENT COGCC-APPROVED REVISION OF THE RULISON SAMPLING AND ANALYSIS PLAN. IN ADDITION TO THE PRODUCED-WATER SAMPLING AND ANALYSIS OUTLINED IN SECTION 5.8 OF THE PLAN, THE OPERATOR SHALL ALSO OBTAIN AND ANALYZE PRODUCED-WATER SAMPLES ON WELLS DESCRIBED IN THE PLAN FOR CONSTITUENTS LISTED IN THE PLAN USING THE SPECIFIC METHOD WHERE APPLICABLE.

Applicable Policies and Notices to Operators

Piceance Rulison Field - Notice to Operators.

NW Colorado Notification Policy.

Attachment Check List

Att Doc Num	Name
400380839	FORM 2 SUBMITTED
400380843	WELL LOCATION PLAT
400384002	DIRECTIONAL DATA
400384003	SURFACE AGRMT/SURETY
400384005	DEVIATED DRILLING PLAN

Total Attach: 5 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Final Review	At request of operator, changed to surface owner = mineral owner. Surface owner signature is not on lease, SUA in place.	4/18/2013 4:34:44 PM
Permit	OK. This well is located within three miles of the Project Rulison well. Email notification of the well has been sent to Rick Hutton with the DOE.	3/18/2013 10:13:06 AM
Engineer	THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 316 FEET DEEP.	2/27/2013 1:14:38 PM
Permit	Pass completeness. Added spacing order as per Operator.	2/25/2013 3:02:16 PM

Total: 4 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Construction	(Not all are used all the time) Terminal Containment, Diversions, Run-On Protection, Tracking, Benching, Terracing, ECM (Erosion Control Mulch), ECB (Erosion Control Blanket), Check Dams, Seeding, Mulching, Water Bars, Stabilized Unpaved Surfaces (Gravel), Stormwater & Snow Storage Containment, Scheduling, Phased Construction, Temporary Flumes, Culverts with inlet & outlet protection, Rip Rap, TRM (Turf Reinforcement Mats), Maintenance, Scheduling, Phased Construction, Fueling BMP's, Waste Management BMP's, Materials Handling BMP's
Wildlife	Minimize the number, length and footprint of oil & gas development roads Use existing routes where possible Combine utility infrastructure planning (gas, electric & water) when possible with roadway planning to avoid separate utility corridors Coordinate Employee transport when possible Reduce visits to well-sites through remote monitoring (i.e. SCADA) and the use of multi-function contractors. Maximize use of state-of-the-art drilling technology (e.g., high efficiency rigs, coiled-tubing unit rigs, closed-loop or pitless drilling, etc.) to minimize disturbance. Reclaim mule deer and elk habitats with native shrubs, grasses, and forbs appropriate to the ecological site disturbed.
Interim Reclamation	Maintenance Revegetation Monitoring BMP maintenance & monitoring Weed Management
Pre-Construction	Wattles, Silt Fence, Vegetation Buffers, Slash, Topsoil Windrows (diversions & ROP's), Scheduling, Phased Construction

Total: 4 comment(s)