



**CEMENTER'S WELL SERVICE, INC.**  
P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

**601135**

Date	10-27-12	Well Owner	Kerr McGee	Well No.	15N-28412	Lease	BARCLAY
County	1265	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (MAJOR-44)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		FL	735		
Surface	7 3/4" ACSG-3644-13 1/2" Hole	Bottom of Surface		FL	724		
Plug		Plug Landed @	678	FL	Time On	1230	
Production		Pipe Landed @	724	FL	Plug Down	1630	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	550	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge	132	Miles		
Fuel Surcharge	132	MILES		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	1539	1544
Disp. Rate	5 BPM	Mixing	1544	1616
Slurry Vol.	1.32 <sup>3</sup> Cu.Ft./Sk	Change Valves	1616	1619
Slurry WL	14.8 - 15.0 PPG	Displacement	1619	1630
Water/Cement	6.25 Gal/SK			
Water Temp.	52°F			
Total Slurry Vol.	189.3	BBLs Cement		
Landed Plug @	750	PSI/Final Lift @	250	PSI
Pre-Flush W/	20	BBLs H <sub>2</sub> O	Tax Reference Code	Sub Total
Displace W/	52.4	BBLs H <sub>2</sub> O	State CO 2.9%	Tax
Circulate	5	BBLs Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		44			
1214/1216		Bulk Truck		44/44			
							2063629
							80012090

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOE, JOSH & ERIC

Received By Randy Hale  
Customer or His Agent