



State
of
Colorado



Krabacher - DNR, Jay

RECEIVED**APR 22 2013****COGCC/Rifle Office****CBL Deferment - 05 045 21838**

2 messages

Soehner, Gage A. <Gage.Soehner@encana.com>

Mon, Apr 22, 2013 at 5:26 PM

To: "Jay Krabacher (Jay.Krabacher@state.co.us)" <Jay.Krabacher@state.co.us>

Cc: "King, Kevin" <Kevin.King@ledcor.com>, "Andrews, David" <David.Andrews@state.co.us>

EnCana CBL Deferment Request

Well Name:	Shideler 19-16C
API Number:	05-045-21838
Pad Name:	O19EB
CIP Date:	4/16/13
CIP Time:	22:00
Top of Gas:	1 st show = 4687' MD, top of planned perms = 5310' MD
Designed TOC:	3212' MD
Temp Log TOC:	4500' MD

Bradenhead Pressure Report

Time	Bradenhead Pressure
6 hours	0
12 hours	0
24 hours	0
48 hours	0
72 hours	0


Comments:

The Shideler 19-16C well on the O19EB pad finished pumping cement and experienced 80% returns throughout the cement job, and due to the losses, the top of cement appears to be 1290' low to plan. Our planned TOC was 3212' MD, and our TOC via temperature log is 4500'

4/23/13

State.co.us Executive Branch Mail - CBL Deferment - 05 045 21838

MD. Our 1st significant gas show was at 4687' MD, and our planned top of perforations (top of commercial gas) is at 5310' MD. The annulus stayed full & static for 4 hours after CIP. We will continue to monitor pressure until a CBL can be performed.



Gage Soehner

Drilling Engineer SRBU

t 720.876.3097

c 720.951.0732

Encana Oil & Gas (USA) Inc.

encana.com

Please note some Encana offices are closed the first and third Friday of each month.

This email communication and any files transmitted with it may contain confidential and or proprietary information and is provided for the use of the intended recipient only. Any review, retransmission or dissemination of this information by anyone other than the intended recipient is prohibited. If you receive this email in error, please contact the sender and delete this communication and any copies immediately. Thank you.

<http://www.encana.com>

 **C920-00060_ENCANA_SHIDELER_19-16C_019EB_TEMP_LOG_Combined.PDF**
570K

Krabacher - DNR, Jay <jay.krabacher@state.co.us>
To: "Soehner, Gage A." <Gage.Soehner@encana.com>
Cc: "King, Kevin" <Kevin.King@ledcor.com>, "Andrews, David" <David.Andrews@state.co.us>

Tue, Apr 23, 2013 at 10:59 AM

Gage:

Encana can defer the CBL on this well.

Regards,

Jay Krabacher
[Quoted text hidden]

—
Jay Krabacher
N W Area Engineer
C O G C C

cosas son mas como son ahora que ellas siempre fueron