

FORM
5A

Rev
06/12

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400408535

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 100322
2. Name of Operator: NOBLE ENERGY INC
3. Address: 1625 BROADWAY STE 2200
City: DENVER State: CO Zip: 80202
4. Contact Name: Kathleen Mills
Phone: (720) 587-2226
Fax: (303) 228-4286

5. API Number 05-123-35088-00
6. County: WELD
7. Well Name: WIEST J
Well Number: 28-65-1HN
8. Location: QtrQtr: NWSW Section: 28 Township: 5N Range: 66W Meridian: 6
9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 11/10/2012 End Date: 11/10/2012 Date of First Production this formation: 11/17/2012

Perforations Top: 7783 Bottom: 11774 No. Holes: 0 Hole size:

Provide a brief summary of the formation treatment: Open Hole: ☐

FRAC'D W/3093610 GAL SILVERSTIM AND SLICK WATER, 3128075# OTTAWA SAND AND 23981# PRO-FLOW PROPPANT

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 73657 Max pressure during treatment (psi): 6722

Total gas used in treatment (mcf): Fluid density at initial fracture (lbs/gal): 8.43

Type of gas used in treatment: Min frac gradient (psi/ft): 0.89

Total acid used in treatment (bbl): Number of staged intervals: 20

Recycled water used in treatment (bbl): 3441 Flowback volume recovered (bbl): 8275

Fresh water used in treatment (bbl): 70216 Disposition method for flowback: RECYCLE

Total proppant used (lbs): 3152056 Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 11/26/2012 Hours: 24 Bbl oil: 239 Mcf Gas: 1210 Bbl H2O: 178

Calculated 24 hour rate: Bbl oil: 239 Mcf Gas: 1210 Bbl H2O: 178 GOR: 5063

Test Method: FLOWING Casing PSI: 2890 Tubing PSI: 2450 Choke Size: 16/64

Gas Disposition: SOLD Gas Type: WET Btu Gas: 1215 API Gravity Oil: 56

Tubing Size: 2 + 7/8 Tubing Setting Depth: 7488 Tbg setting date: 11/19/2012 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Kathleen Mills

Title: Regulatory Analyst

Date: _____

Email kmills@nobleenergyinc.com

:

Attachment Check List

Att Doc Num	Name

Total Attach: 0 Files

General Comments

User Group Comment Comment Date

--	--	--

Total: 0 comment(s)