

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400404721

Date Received:

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER ☐  
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒

Refiling ☒

Sidetrack ☐

PluggingBond SuretyID

20030063

3. Name of Operator: RENEGADE OIL & GAS COMPANY LLC

4. COGCC Operator Number: 74165

5. Address: 6155 S MAIN STREET #210

City: AURORA State: CO Zip: 80016

6. Contact Name: J. B. CONDILL Phone: (303)680-4725 Fax: (303)680-4907

Email: JBCROG@AOL.COM

7. Well Name: NORDMAN ESTATE Well Number: 10-2

8. Unit Name (if appl):  Unit Number:

9. Proposed Total Measured Depth: 8500

WELL LOCATION INFORMATION

10. QtrQtr: NWNE Sec: 10 Twp: 6S Rng: 64W Meridian: 6

Latitude: 39.547980 Longitude: -104.538390

Footage at Surface: 750 feet FNL/FSL 1832 feet FEL/FWL FEL

11. Field Name: CALEDONIA Field Number: 9660

12. Ground Elevation: 5992.38 13. County: ELBERT

14. GPS Data:

Date of Measurement: 01/18/2011 PDOP Reading: 2.3 Instrument Operator's Name: KEITH WESTFALL

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL  FEL/FWL  Bottom Hole: FNL/FSL  FEL/FWL

Sec:  Twp:  Rng:  Sec:  Twp:  Rng:

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 155 ft

18. Distance to nearest property line: 1410 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1350 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
D SAND	DSND			
J SAND	JSND			
NIOBRARA-CODELL	NB-CD			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #:

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
T6S, R64W, SEC 3: LOTS 3, 4, S/2 NW/4, SW/4, S/2 S/2 SE/4, SEC 10: W/2 NW/4, NE/4

25. Distance to Nearest Mineral Lease Line: 823 ft 26. Total Acres in Lease: 600

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	425	400	425	0
1ST	7+7/8	4+1/2	11.6	0	8,500	250	8,500	7,000
			Stage Tool		2,500	575	2,500	0

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments This is a refile of a permit that will expire on 5/18/2013 and we will not spud the well by then. Nothing has changed and all of the originally submitted attachments are still valid. The approved Form 2A expires on 5/18/2014. We intend to drill this well prior to that expiration. Location and rig will be situated to comply with the 150' setback requirement from an above ground utility. We will drill this well with either a "super single" rig that is 70' tall or a double that is 102' tall. There will be no conductor casing set.

34. Location ID: 423259

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: J. B. Condill

Title: VP Land Date: \_\_\_\_\_ Email: jbcrog@aol.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

#### API NUMBER

05 039 06671 00

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

#### CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Data retrieval failed for the subreport 'IntPolicy\_NTO' located at: W:\netpub\Net\Reports\policy\_nto.rdl. Please check th

### Attachment Check List

Att Doc Num	Name

Total Attach: 0 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

### BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)