

FORM  
5Rev  
02/08

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400409011

Date Received:

## DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 96850

4. Contact Name: Sandra Salazar

2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

Phone: (303) 629-8456

3. Address: 1001 17TH STREET - SUITE #1200

Fax: (303) 629-8268

City: DENVER State: CO Zip: 80202

5. API Number 05-045-21476-00

6. County: GARFIELD

7. Well Name: Hoeppli

Well Number: RWF 24-36

8. Location: QtrQtr: SENW Section: 36 Township: 6S Range: 94W Meridian: 6

Footage at surface: Distance: 2630 feet Direction: FNL Distance: 2616 feet Direction: FWL

As Drilled Latitude: 39.482253 As Drilled Longitude: -107.836712

## GPS Data:

Date of Measurement: 08/09/2012 PDOP Reading: 3.0 GPS Instrument Operator's Name: Jack Kirkpatrick

\*\* If directional footage at Top of Prod. Zone Dist.: 967 feet. Direction: FSL Dist.: 2243 feet. Direction: FWL

Sec: 36 Twp: 6S Rng: 94W

\*\* If directional footage at Bottom Hole Dist.: 949 feet. Direction: FSL Dist.: 2236 feet. Direction: FWL

Sec: 36 Twp: 6S Rng: 94W

9. Field Name: RULISON

10. Field Number: 75400

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 11/27/2012 13. Date TD: 12/06/2012 14. Date Casing Set or D&amp;A: 12/07/2012

## 15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 8973 TVD\*\* 8678 17 Plug Back Total Depth MD 8853 TVD\*\* 8558

18. Elevations GR 6528 KB 6554

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

## 19. List Electric Logs Run:

RPM/CBL/MUDLOGS

## 20. Casing, Liner and Cement:

## CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	24	18	48	0	63	24	0	63	VISU
SURF	13+1/2	9+5/8	32.3	0	1,175	320	0	1,175	VISU
1ST	8+3/4	4+1/2	11.6	0	8,963	1,320	5,190	8,963	CBL

**STAGE/TOP OUT/REMEDIAL CEMENT**

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

**FORMATION LOG INTERVALS AND TEST ZONES**

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WASATCH G	2,592		<input type="checkbox"/>	<input type="checkbox"/>	
MESAVERDE	5,217		<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO	8,033		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	8,871		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

Please note: The "as-drilled" GPS information provided is actual data of the existing well conductor location prior to the big rig spud date.

Surface Pressure = 0

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Sandra Salazar

Title: Permit Technician II

Date:

Email: sandra.salazar@wpenergy.com

**Attachment Check List**

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400409012	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400409013	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400409016	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

**General Comments****User Group**      **Comment****Comment Date**

--	--	--

Total: 0 comment(s)