

FORM
2

Rev
12/05

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400393715

Date Received:

03/28/2013

PluggingBond SuretyID

20100017

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE COMMINGLE

Refiling

Sidetrack

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Jevin Croteau Phone: (720)876-5339 Fax: (720)876-6339

Email: jevin.croteau@encana.com

7. Well Name: Devore Well Number: 1H-34H

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 11807

WELL LOCATION INFORMATION

10. QtrQtr: NENE Sec: 34 Twp: 3N Rng: 66W Meridian: 6

Latitude: 40.188280 Longitude: -104.758410

Footage at Surface: 231 feet FNL 1298 feet FEL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4961 13. County: WELD

14. GPS Data:

Date of Measurement: 01/16/2013 PDOP Reading: 2.4 Instrument Operator's Name: John rice

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
726 FNL 102 FEL 460 FSL 100 FEL
Sec: 34 Twp: 3N Rng: 66W Sec: 34 Twp: 3N Rng: 66W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 230 ft

18. Distance to nearest property line: 231 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 177 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR		320	GWA

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No: Surface Owners Agreement Attached or \$25,000 Blanket Surface Bond \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

SHL lease = NE of section 34, T3N, R66W. The attached lease map shows the entire Encana lease hold covered by the wellbore, which equals 320 total acres. The horizontal wellbore crosses lease lines in the GWA spacing unit.

25. Distance to Nearest Mineral Lease Line: 0 ft 26. Total Acres in Lease: 160

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? Yes No

31. Mud disposal: Offsite Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: Land Farming Land Spreading Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	22	16	30	0	80	80	80	0
SURF	12+1/4	9+5/8	40	0	800	100	800	0
1ST	8+3/4	7	26	0	7,725	437	7,725	500
2ND	6+1/8	4+1/2	13.5	0	11,807	168	11,807	168

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments Encana requests the approval of a 318A(l).a.(1) and 318A(l).c(1) exception location as the well head is to be located outside of a GWA drilling window, further than 50' from an existing well. Request letter and waivers attached. Encana also requests the approval of the omission of open hole logs, request letter attached. Proposed spacing unit is E/2E/2 of Sec.34 and W/2W/2 of Sec.35 T3N R66W. The distance to nearest well permitted/completed in the same formation (BHL) was measured from the Brown 33-35, API #: 05-123-27153.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Jevin Croteau

Title: Regulatory Analyst Date: 3/28/2013 Email: jevin.croteau@encana.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 4/27/2013

API NUMBER
05 123 37232 00

Permit Number: _____ Expiration Date: 4/26/2015

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide notice of MIRU via an electronic Form 42.
- 2) Comply with Rule 317.i and provide cement coverage to a minimum of 200' above the Niobrara. Verify cement coverage with a cement bond log per 317.o.

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area.

Attachment Check List

Att Doc Num	Name
400393715	FORM 2 SUBMITTED
400393725	WELL LOCATION PLAT
400393726	DEVIATED DRILLING PLAN
400393727	EXCEPTION LOC REQUEST
400393728	OTHER
400393729	PROPOSED SPACING UNIT
400393730	SURFACE AGRMT/SURETY
400393731	30 DAY NOTICE LETTER
400393732	MINERAL LEASE MAP
400393733	DIRECTIONAL DATA
400397103	OFFSET WELL EVALUATION

Total Attach: 11 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Changed Mud Disposal to Offsite/Land Farming to match the 2A. Deleted Spacing Order Number and corrected Unit Configuration to GWA. Above changes were ok'd by operator. Exception Location Request and Waiver are in the same attachment. Requested that operator separate them in the future. Horizontal wellbore crosses lease lines within drilling and spacing unit; distance to lease line is 0'; distance to unit boundary is 460'. Ready to pass pending public comment.	4/9/2013 1:41:04 PM
Engineer	Evaluated offset wells for adequate cement coverage.	4/4/2013 10:53:38 AM
Permit	Passes completeness.	3/29/2013 10:16:51 AM

Total: 3 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Drilling/Completion Operations	Encana will comply with the "COGCC Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area", dated May 29, 2012.
Drilling/Completion Operations	<p>Best Management Practice for a Horizontal Wellbore Fracturing Stimulation</p> <ol style="list-style-type: none">1. At least seven (7) days prior to fracture stimulation, the operator is to notify all operators of non-operated wells within 300 feet of the wellbore to be fracture stimulated of the anticipated date stimulation date and the recommended best management practice to shut-in all wells within 300' of the stimulated wellbore completed in the same formation.2. The operator will monitor the bradenhead pressure of all wells within 300 feet of the well to be fracture stimulated.3. Bradenhead pressure gauges are to be installed 24 hours prior to stimulation. The gauges are to read at least once during every 24-hour period until 24-hours after stimulation is completed (post flowback). The gauges are to be of the type able to read current pressure and record the maximum encountered pressure in a 24-hour period. The gauge is to be reset between each 24-hour period. The pressures are to be recorded and saved.4. If at any time during stimulation or the 24-hour post-stimulation period, the bradenhead annulus pressure of the treatment well or offset wells increases more than 200 psig, as per Rule 341, the operator of the well being stimulated shall verbally notify the Director as soon as practicable, but no later than twenty-four (24) hours following the incident. Within fifteen (15) days after the occurrence, the operator shall submit a Sundry Notice, Form 4, giving all details, including corrective actions taken.
Drilling/Completion Operations	<p>Anti-collision BMP:</p> <p>Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as-constructed gyro survey will be submitted to COGCC with the Form 5.</p>

Total: 3 comment(s)