

FORM  
5A

Rev  
06/12

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400410914

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 100322  
2. Name of Operator: NOBLE ENERGY INC  
3. Address: 1625 BROADWAY STE 2200  
City: DENVER State: CO Zip: 80202  
4. Contact Name: Eileen Roberts  
Phone: (303) 2284330  
Fax: (303) 2284286

5. API Number 05-123-34152-00  
6. County: WELD  
7. Well Name: FISCUS LD  
Well Number: 22-76HN  
8. Location: QtrQtr: SESW Section: 22 Township: 9N Range: 58W Meridian: 6  
9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 08/07/2012 End Date: 08/07/2012 Date of First Production this formation: 08/18/2012

Perforations Top: 6367 Bottom: 9958 No. Holes: 0 Hole size:

Provide a brief summary of the formation treatment: Open Hole: ☐

Frac'd the Niobrara w/ 2682760 gals of Silverstim and Slick Water with 3,030,000#'s of Ottawa sand.

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 130933 Max pressure during treatment (psi): 6491

Total gas used in treatment (mcf): 0 Fluid density at initial fracture (lbs/gal): 8.43

Type of gas used in treatment: Min frac gradient (psi/ft): 0.92

Total acid used in treatment (bbl): 0 Number of staged intervals: 20

Recycled water used in treatment (bbl): 67058 Flowback volume recovered (bbl): 12584

Fresh water used in treatment (bbl): 63875 Disposition method for flowback: RECYCLE

Total proppant used (lbs): 2907497 Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 08/22/2012 Hours: 24 Bbl oil: 714 Mcf Gas: 280 Bbl H2O: 522

Calculated 24 hour rate: Bbl oil: 714 Mcf Gas: 280 Bbl H2O: 522 GOR: 392

Test Method: FLOWING Casing PSI: 430 Tubing PSI: 0 Choke Size: 024/64

Gas Disposition: SOLD Gas Type: WET Btu Gas: 1223 API Gravity Oil: 38

Tubing Size: 2 + 7/8 Tubing Setting Depth: 6095 Tbg setting date: 08/14/2012 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

\*\* Bridge Plug Depth: \*\* Sacks cement on top: \*\* Wireline and Cement Job Summary must be attached.

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Eileen Roberts \_\_\_\_\_

Title: Regulatory Specialist Date: \_\_\_\_\_ Email: eroberts@nobleenergyinc.com  
:

### Attachment Check List

Att Doc Num	Name

Total Attach: 0 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)