



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 338220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

601045

Date	8/23/2012	Well Owner	Kerr McGee	Well No.	29-29	Lease	SADDLEBACK
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME #11)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	890		
Surface	8 5/8" CSG 24"	Bottom of Surface		Fl.	878		
Plug		Plug Landed @	836	FL	Time On	1600	
Production		Pipe Landed @	878	FL	Plug Down	1915	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neet TYPE III 100% EXCESS	590	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge	240	Miles		
Fuel Surcharge	240	MILES		
Additional Cement 1" 80 FT TO SURFACE	190	SKS		
Mixing Rate 4 BPM	Pre-Flush	1830	1836	
Disp. Rate 5 BPM	Mixing	1836	1908	
Slurry Vol. 1.32 ³ Cu.Ft./Sk	Change Valves	1908	1911	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	1911	1915	
Water/Cement 6.25 Gal/SK				
Water Temp. 62				
Total Slurry Vol. 183.3	BBLS Cement			
Landed Plug @ 900	PSI/Final Lift @ 400	PSI		
Pre-Flush W/ 30	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ 53.1	BBLS H ₂ O	State CO 2.9%	Tax	
Circulate 0	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		60			
1217/1214/1216		Bulk Truck		60/60/60			

We do not assume any responsibility for any damages or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim/ADAM/marcos

Received By

Customer or H/E Agent