

Magna Energy Services, LLC

17509 County Road 14,

Ft. Morgan, CO 80701

(970)-867-9007

Fax (970)-867-8374

Job Log

Date: 3/18/2103 - 3/27/2103

Operator: Noble Energy

Well name: Gill land 1

Location: SENE, section:22, T6N, R64W

3/18/2013: MIRU P&A equipment

3/19/2013: ND wellhead and NU BOP, worked tubing free, could not circulate wellbore. RU wireline, TIH with junk basket to 5,400', TOH, PU tubing punch, TIH and perf tubing at 5,398', TOH, RD wireline, SWI, SDFD.

3/20/2013: Circulate wellbore with 80 bbl. of water, TOH, PU bit, TIH to 6,597', Circulate wellbore with 80 bbl. of water, SWI, SDFD.

3/21/2013: Circulate wellbore with 80 bbl. of water, RU wireline, Gyro wellbore, TOH, RD wireline, TOH tubing and LD bit. PU CIBP, TIH and set CIBP at 6,548', mixed and pumped 10 sxs of 15.8# class G cement, displaced cement with 24 bbl. of water, TOH, SWI, SDFD.

3/22/2013: RU wireline, TIH with split shot and cut casing at 5,199', TOH and RD wireline. ND BOP, ND wellhead, could not pull casing, (change of procedure to not pull casing), NU wellhead, NU BOP, SWI, SDFD.

3/25/2013: RU JW wireline, TIH and run CBL, TOH, TIH and perf casing at 5,180', TOH to 2,500' and perf casing, TOH and RD wireline. PU CICR on tubing, TIH and set CICR at 5,077', mix and pump 90 sxs of class G cement under CICR, mix and pump 10 sxs of class G cement on top CICR, TOH and PU CICR, TIH and set CICR at 2,408' mix and pump 40 sxs of class G cement under CICR, mix and pump 10 sxs of class G cement on top of CICR, SWI, SDFD.

3/26/2013: RU wireline, TIH to 550' and perf casing, TOH and RD wireline. PU CICR on tubing, TIH and set CICR at 455', mix and pump 147 sxs of class G cement under CICR, mix and pump 37 sxs of class G cement on top of CICR (TOC at surface), TOH, SWI, SDFD.

3/27/2013: Dig out and cut off well head, weld info cap onto casing, back fill pit, P&A complete

Cementing Contractor: Magna Energy Services, LLC

Cementing Contractor supervisor: Adam Chastain

Operations Supervisor: Kelly Reinhardt

COGCC Representative: James Precup

Wireline Contractor: Magna Energy Services, LLC/JW-Wireline