

# Pehr Pooling Unit 2 05-123-10869- Proposed WBD (P&A)

12-1/4" Surface Hole

7-7/8" Prod Hole

## Existing

KB: 4955  
GL: 4944

9 5/8" Surf Csg Shoe @ 815  
Base Fox Hills @ BHP

Current TOC @ 4400  
Top of Sussex @ 4583

NB Top @ 7230

CD perfs @ 7549-7572

JS perfs @ 8000-8030  
5 1/2" Prod Csg @ 8150  
TD @ 8150

## Planned

30 sx of cement

Welded Cap  
Surface plug 11'-100'  
CIBP @ 100'

100 sx of cement (0.0238 bbl/Inft  
PC, 7.875 " OH (60% excess),  
0.0744 bbl/Inft SC )

cut casing @ 915'  
Stub Plug @ 615'-965'

Balanced plug @ 4483-4683

20 sx of cement (0.0238 bbl/Inft  
)

65 sx of cement (0.0238 bbl/Inft )

Balanced plug @ 6830'-7490'  
CIBP @ 7490

CIBP @ 7930' w/ min 2 sx cmnt

