



FOR OGCC USE ONLY

Date Received: 1/7/2010
Doc Num: 2609128

WELL ABANDONMENT REPORT

Submit original plus one copy. This form is to be submitted as an intent whenever a plugging is planned on a borehole. The approved intent shall be valid for six (6) months after the approval date; after that period a new intent will be required. After the plugging is complete, this form and one copy shall again be submitted along with third party cement verification as a subsequent report of the work as actually completed.

OGCC Operator Number: 69175	Contact Name and Telephone	24-hour Contact (required)
Name of Operator: PETROLEUM DEVELOPMENT CORPORATION	LARRY ROBBINS	
Address: 120 GENESIS BLVD CHARLES	Phone: 304 842-3597	
City: BRIDGEPORT State: WV Zip: 26330	Fax: 304 808-0913	Tel:

API Number: 05-045-13353 00	OGCC Lease No.:	Other wells in this lease?
Well Name: PUCKETT	Well Number: 24B-6	
Location (QtrQtr, Sec, Twp, Rng, Mer):	SESW Sec 6 T 7S R 96W PM 6	
County: GARFIELD	Federal, Indian, or State Lease Number:	
Field Name: GRAND VALLEY	Field Number: 31290	

Attachment Checklist	Doc Num

Subsequent Report of Abandonment

Only Complete the Following Background Information for Intent to Abandon

Reason for Abandonment: _____

Casing to Be Pulled: _____ Top of Casing Cement: _____

Fish in Hole: _____

Wellbore has Uncemented Casing Leaks: _____

Details: _____

Current and Previously Abandoned Zones					
Formation code	Perf Top	Perf Bottom	Date Abandoned	Method of Isolation	Plug Depth

Casing History				
Casing String	Casing Size	Casing Depth	Cement Top	Cement Bottom
CONDUCTOR	20 /	100	0	100
SURF	9 5/8	2858	0	2858
1ST	7 /	5397		5397
OPEN HOLE	/	7460		

Plugging Procedure for Intent and Subsequent Report

Set 72 sacks cement from 5597 ft. to 5197 ft. in OPEN HOLE - ACROSS INTERMEDIATE (7" CSG) - DA
Perforate and squeeze at 2853 ft. with 37 sacks. Leave at least 100 ft. in casing. SHOE

Set 64 sacks at surface.

Cut all casing strings four feet below ground level, weld on plate Dry-Hole Marker :

Set sacks in rat hole. Set sacks in mouse hole.

Additional Plugging Information for Subsequent Report Only

Casing Recovered: _____ ft. of _____ inch casing.	Plugging Date: 7/7/2006
*Wireline Contractor: ROCKY MTN WIRELINE	*Cementing Contractor: BJ SERVICES CO.
Type of Cement and Additives Used: CLASS G, 2% CACI2	*Attach Job Summaries

I hereby certify that the statements made in this form are, to the best of my knowledge, true, correct, and complete.

Print Name: LARRY ROBBINS

Signed? Yes Title: REGULATORY AGENT Date: 1/6/2010

OGCC Approved: ANDREWS, DAVID Title: PE II Date: 5/6/2013

CONDITIONS OF APPROVAL, IF ANY: David Andrews