

Bochius Pooling UT 1 05-123-07284- Proposed WBD (P&A)

12-1/4" Surface Hole

7-7/8" Prod Hole

Existing

KB: 4744
GL: 4732

8 5/8" Surf Csg Shoe @ 362
Base Fox Hills @ BHP

Top of Sussex @ 4135
Base of Shannon @ 5247

NB Top @ 6776
Current TOC @ 6900

JS perfs @ 7546'-7581'

4 1/2" Prod Csg @ 7680
TD @ 7670

Planned

30 sx of cement

Welded Cap
Surface plug 12'-100'
CIBP @ 100'

170 sx of cement (0.0155 bbl/lnft
PC, 13" caliper OH, 0.0636
bbl/lnft SC & 20% excess) 1.53
cuft/sx

cut casing @ 465'
Stub Plug @ 100'-515'

1300 sx of cement (12" caliper, 20%
excess) 1.15 cuft/sx

Squeeze holes @ 3900
CICR @ 3930' w/ 2 sx of cement
Squeeze holes @ 5450

165 sx of cement (9" caliper & 20%
excess) 1.71 cuft/sx

TOC @ 6375'
CICR @ 6400' w/ 2 sx cmnt

Squeeze holes @ 6880'

CIBP @ 7486' w/ min 2 sx of cmnt

