

US ROCKIES REGION

Anadarko Daily Summary Report

Well: SADDLEBACK 6-29X

Project:COLORADO-WELD-NAD83-UTM13

Site:SADDLEBACK 18-29

Rig Name No: XTC 11/11, XTC 11/11

Event: DRILLING

Start Date: 6/16/2012

End Date: 8/4/2012

Spud Date: 7/22/2012

Active Datum: RKB @5,031.00usft (above Mean Sea Level)

UWI: 0/2/N/67/W/29/O/NW/6/O/O/O/O/O/O/O

Report No	Report Date	MD (usft)	24 Hr Summary
1	07/22/2012	63	RIGDOWN AND MOVE RIG, RIG UP AND SPUD WELL @ 23:30
2	07/23/2012	2163	DRILL SURFACE TO TD (890') CIRC, TTO W/ DP AND TOOLS, RUN SURFACE CASING, CEMENT SURF W/ TOP JOB, WOC, NU AND TEST BOP'S TIH W/ PROD BHA, DRILL OUT CASING SHOE, DRILL PRODUCTION HOLE
3	07/24/2012	7759	DRILL PROD HOLE FROM 2163 TO 7759
4	07/25/2012	8328	DRLG. 7759-8328, CIRC. SWEEPS, WIPER TRIP, CIRC. SWEEPS, LDDP,
5	07/26/2012	8328	LDDP & TOOLS, LOGGED, (CODELL FAULTED OUT) MOVE CASING OFF RACKS, BRING OVER DRILL PIPE FOR SETTING PLUGS, STRAP PIPE, TRIP IN DRILL PIPE TO PLUGGING DEPTH, CIRC., CEMENT 1st PLUG(7806-7275), TRIP OUT, CIRC., TRIP OUT TO 4828, SET PLUG (4828-4178)
6	07/27/2012	8328	FINISH DISPLACING PLUG #2, TRIP OUT TO 4056, CIRC., RUN IN 2 JOINTS TO 7158, CEMENT 3rd PLUG, LDDP, NIPPLE DOWN BOPE, RIG RELEASED @ 0600
7	07/31/2012	3935	SKID RIG, RIG UP, NIPPLE UP, WORK ON BOP TRACKS/SHEAVES, PU TOOLS, TRIP IN KICK OFF PLUG, DRILL 3889-4700
8	08/01/2012	6950	DRLG 3935-4071, RS, DRLG. 4071-4809, LOST RETURNS (BOOTED UP) LD 2 JTS., GOT RETURNS, REAMED 2 JT, DRLG. 4809-4933, RS, DRLG. 4933-4989, FILTERS IN GEN SET, DRLG. 4989-5160, R & R TD ENCODER, DRLG. 5160-5251, CHANGE FUEL PUMP FOR GEN SETS, DRLG. 5251-6950
9	08/02/2012	7842	DRLG. 6950-7610, WORK TIGHT HOLE, DRLG. 7610-7653, GAS KICK, CIRC. GAS OUT (NO FLARE), KILL WELL, DRLG 7610-7842, TRIP OUT 6 JTS. TO REGAIN CIRC., CONDITION MUD FOR LOST CIRC. ZONE.
10	08/03/2012	8297	WASH TO BOTTOM, DRLG. 7842-8297, CIRC., LDDP & TOOLS, RIG UP CASERS, RUN CASING
11	08/04/2012	8297	RIH w/ CASING TO 5000', REPAIR COMM. LINK, RIH TO 5885', CIRC. GAS, INSTALL ROT. HEAD, SPOT 11.7# PILL, BLEED DOWN PRESSURE, RIH w LAST 54 JOINTS CASING, CIRC., CEMENT 3 STAGES, NIPPLE DOWN, SET SLIPS, RIG DOWN FOR SKID RIG RELEASED @ 22:00, 8/4/2012