

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400404418

Date Received:

04/16/2013

PluggingBond SuretyID

20090025

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☒

Sidetrack ☐

3. Name of Operator: AUGUSTUS ENERGY PARTNERS LLC

4. COGCC Operator Number: 10275

5. Address: P O BOX 250

City: WRAY State: CO Zip: 80758

6. Contact Name: Loni Davis Phone: (970)332-3585 Fax: (970)332-3587

Email: ldavis@augustusenergy.com

7. Well Name: Crossland Well Number: 43-28 5N46W

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 2970

WELL LOCATION INFORMATION

10. QtrQtr: NESE Sec: 28 Twp: 5N Rng: 46W Meridian: 6

Latitude: 40.371790 Longitude: -102.495180

Footage at Surface: 2032 feet FNL/FSL 792 feet FEL/FWL FEL

11. Field Name: Wages Field Number: 90460

12. Ground Elevation: 3881 13. County: YUMA

14. GPS Data:

Date of Measurement: 04/03/2013 PDOP Reading: 2.8 Instrument Operator's Name: Kevin McCormick

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 790 ft

18. Distance to nearest property line: 595 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1141 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR			318B

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

5N46W, Sec 28: SE/4, E2SW

25. Distance to Nearest Mineral Lease Line: 595 ft

26. Total Acres in Lease: 240

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Evaporation and Burial

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	9+7/8	7	17	0	545	200	545	0
1ST	6+1/4	4+1/2	10.5	2170	2,970	200	2,970	0

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments No conductor casing will be used. The APD expired 09/07/12, all conditions remain the same on the refilling. The Form 2A will expire 09/07/13, refilling it as well, since it may expire before we drill the well.

34. Location ID: 411583

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Loni J. Davis

Title: Oper. Acctg & Reg Spec Date: 4/16/2013 Email: ldavis@augustusenergy.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 5/11/2013

API NUMBER

05 125 09827 00

Permit Number: _____ Expiration Date: 5/10/2015

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 48 hour notice prior to spud via electronic Form 42.
- 2) Set surface casing at least 50' into Pierre Shale for aquifer coverage, (545' minimum - as proposed).
- 3) If completed, provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 4) If dry hole, set 35 sks cement 50' above Niobrara top, 35 sks cement ½ out, ½ in surface casing, 10 sks cement at top of surface casing, cut casing 4' below GL, weld on plate, 5 sks cement in rat hole & 5 sks cement in mouse hole.

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

Attachment Check List

Att Doc Num	Name
400404418	FORM 2 SUBMITTED
400404435	30 DAY NOTICE LETTER
400404437	SURFACE AGRMT/SURETY
400404438	TOPO MAP
400404555	WELL LOCATION PLAT

Total Attach: 5 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final review completed. No LGD or public comments.	5/8/2013 10:40:14 AM
Permit	Rule 318B is in effect.	4/25/2013 7:06:57 AM
Permit	Changed the well name as per operator request.	4/17/2013 10:08:17 AM

Total: 3 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Drilling/Completion Operations	<p>Best Management Practices Northern Yuma County, Colorado</p> <p>To address construction during drilling and all other operations associated with Oil and Gas development throughout Northern Yuma County, Colorado area StormWater Management Plans(SWMP) are in place and in compliance with the Colorado Department of Health and Environment (CDPHE) under Permit # COR-039921.</p> <p>Best Management Practices (BMP's) will be reviewed and maintained prior to, during and after construction of drilling site, laying of flowlines, installation of surface equipment and reclamation of site. Each location's BMP's will vary according to terrain and phase of construction and will be implemented in accordance to SWMP.</p> <p>Regular location inspections will be performed and any BMP's not effectively working will be documented and resolved in a timely manner.</p> <p>Spill Prevention, Control and Countermeasures will be implemented. Should any spills occur they will be cleaned up immediately and effectively to minimize any integration with storm water runoff. General good housekeeping practices will be performed to keep spills at a minimum.</p>

Total: 1 comment(s)