



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

601073

Date <u>9/28/12</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>29N-28H2</u>	Lease <u>Ariles</u>				
County <u>Weld</u>	State <u>Colorado</u>						
Charge to <u>Kerr McGee Oil &amp; Gas Onshore, LP</u>							
Address <u>1999 Broadway, Suite 3700 (MAJOR 44)</u>							
City, State Zip <u>Denver, Colorado 80202</u>							
Type of Job	Depth	Ft. <u>956</u>					
Surface <u>5 5/8" 150-40" 13 1/2 166</u>	Bottom of Surface	Ft. <u>945</u>					
Plug	Plug Landed @ <u>900</u>	Fl. Time On <u>2345</u>					
Production	Pipe Landed @ <u>945</u>	Fl. Plug Down <u>0300</u>					
Description	Qty.	Meas.	Unit Price Amount				
Set Up Charge	1						
Cement Neat <u>Type III</u>	700	SKS					
Poz. Mix							
Calcium Chloride	2.5	%					
Gel % Flo-Crete 1/4 # Per Sack							
Mileage Charge	130	Miles					
Fuel Surcharge	130	Miles					
Additional Cement		SKS					
Mixing Rate 4 BPM	Pre-Flush	0206-0212					
Disp. Rate 5 BPM	Mixing	0212-0243					
Slurry Vol. 1.32 <sup>3</sup> Cu.Ft./Sk	Change Valves	0243-0246					
Slurry Wt. 14.8 - 15.0 PPG	Displacement	0246-0300					
Water/Cement 6.25 Gal/SK							
Water Temp. <u>104°F</u>							
Total Slurry Vol. <u>1104.5</u>	BBS Cement						
Landed Plug @ <u>400</u>	PSI/Final Lift @ <u>200</u>	PSI					
Pre-Flush W/ <u>30</u>	BBS H <sub>2</sub> O	Tax Reference Code	Sub Total				
Displace W/ <u>109.7</u>	BBS H <sub>2</sub> O	State <u>CO 2.9%</u>	Tax				
Circulate <u>5</u>	BBS Cement		Total				
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>44</u>		<u>2054.303</u>	
<u>1210/1218</u>		Bulk Truck		<u>44/44</u>		<u>6012090</u>	

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin Francis Steve

Received By [Signature]  
Customer or His Agent