

FORM
5

Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400421112

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 100322

4. Contact Name: Kathleen Mills

2. Name of Operator: NOBLE ENERGY INC

Phone: (720) 587-2226

3. Address: 1625 BROADWAY STE 2200

Fax: (303) 228-4286

City: DENVER State: CO Zip: 80202

5. API Number 05-123-35333-00

6. County: WELD

7. Well Name: WELLS RANCH AA

Well Number: 24-65HN

8. Location: QtrQtr: SWSW Section: 24 Township: 6N Range: 63W Meridian: 6

Footage at surface: Distance: 2166 feet Direction: FNL Distance: 224 feet Direction: FWL

As Drilled Latitude: 40.473350 As Drilled Longitude: -104.393650

GPS Data:

Date of Measurement: 08/16/2012 PDOP Reading: 1.9 GPS Instrument Operator's Name: PAUL TAPPY

** If directional footage at Top of Prod. Zone Dist.: 2605 feet. Direction: FNL Dist.: 884 feet. Direction: FWL

Sec: 24 Twp: 6N Rng: 63W

** If directional footage at Bottom Hole Dist.: 2610 feet. Direction: FNL Dist.: 542 feet. Direction: FEL

Sec: 24 Twp: 6N Rng: 63W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 08/30/2012 13. Date TD: 09/05/2012 14. Date Casing Set or D&A: 09/06/2012

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 10957 TVD** 6603 17 Plug Back Total Depth MD 11936 TVD** 6582

18. Elevations GR 4807 KB 4831

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL, NO OTHER LOGS RUN

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	24	16	75	0	124	80	0	124	VISU
SURF	13+3/4	9+5/8	36	0	631	349	0	631	VISU
1ST	8+3/4	7	26	0	7,051	560	594	7,051	CALC
1ST LINER	6+1/8	4+1/2	11.6	6913	10,937	0			

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PIERRE	2,869		<input type="checkbox"/>	<input type="checkbox"/>	
PARKMAN	3,602		<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	4,416		<input type="checkbox"/>	<input type="checkbox"/>	
SHANNON	4,961		<input type="checkbox"/>	<input type="checkbox"/>	
TEEPEE BUTTES	5,771		<input type="checkbox"/>	<input type="checkbox"/>	
NIORARA	6,562		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Kathleen Mills

Title: Regulatory Analyst Date: _____ Email: kmills@nobleenergyinc.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400421146	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400421147	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400421136	LAS-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400421137	PDF-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400421148	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group

Comment

Comment Date

--	--	--

Total: 0 comment(s)