

US ROCKIES REGION

Anadarko Daily Summary Report

Well: UPRR 22 PAN AM "C" #1

Project: COLORADO-WELD-NAD83-UTM13	Site: UPRR 22 PAN AM "C" #1	Rig Name No: CONCORD 3/3
Event: ABANDONMENT	Start Date: 3/7/2013	End Date: 5/3/2013
Active Datum: RKB @4,962.99usft (above Mean Sea Level)		UWI: 0/3/N/66/W/27/0/SWNE/6/0/0/0/0/0/0

Report No	Report Date	MD (usft)	24 Hr Summary
1	03/07/2013		MIRU concord rig # 3 blew down well & kill it W 50 bbls ND WH NU BOP's tally out 250 jts 2 3/8, RU J-W wireline. RIH W/ junk basket/ gauge ring to 7800. PU & RIH W/ 4 1/2 CIBP set it @ 7780 with 2 sks of cement on top. PU and RIH W/ 4 1/2 CIBP set it.
2	03/08/2013		Crew to loc, RU J-W wireline Log well from 7115 to surface, TIH W/ 227 jts 2 3/8 to 7115, RU sanjel pump 30 sks of thermal 35. LD 23 jts reverse out & pump 70 bbls of drilling mud, TOO H lay down 72 jts & stand back 132 jts SWI crew to yard
3	03/11/2013		Crew to loc, RU J-W wireline shoot squeeze holes @ 5400 & 4170 & set CICR @ 4185, RU tester test in 134 jts 2 3/8 RD tester sting into CICR, RU sanjel pump 600 sks class G cement & 20 bbls of well seal last circulation with 4 bbls left pump displacement.
4	03/12/2013		Crew to loc, RU wireline shoot squeeze holes @ 560, Pump into 2 bbls a minute @ 550 psi didn't get circulation up surface, wireline RIH set CICR @ 450, RU sanjel & pump 20 bbls of SMS & 100 sks type III cement W/ cello flake pump 50 sks & pump 10 sks.
5	03/13/2013		Crew to loc, pump into SQZ holes 1/4 bbl a minute at 600 psi, RU sanjel pump 25SCKS 4 1/2 bbls pressure up to 875 stop 5 min & pump to a 1050, Pump 3 times to 1050 was holding good sting out pump 2 bbls on top of CICR RD sanjel LD tbg SWI crew to yard.
6	03/14/2013		Crew to loc, PU 8 jts tag cement @ 230 ft pressure test casing to 1000 psi held good, ND BOP's rock out pump & tank rig down.
7	05/03/2013		Crew travel, safety. Dug up casing. Cut casing, removed wellhead. Tagged cement in 4.5" csg @ 100". Filled w 6 bags 5000# cement. Filled surface w 3 bags 5000# cement. Capped casing w plate containing well info. Backfilled.
8	05/03/2013		TIME ON: 11:0, ROUTE: S44, WINS: 74893, PROJECT TYPE: P&A, PROD: NB/CD/J, TP: N/A, CP: N/A, CHOKE: N/A, BATT #: 36000040, GATHERER: KMG, STAT #: 07317, LINE #: 16-258-6, COMMENTS: P&A'd OFFLINE.