

## US ROCKIES REGION

## Anadarko Daily Summary Report

Well: TUTTLE J BURTON GU #1

Project:COLORADO-WELD-NAD83-UTM13

Site:BELLA 14-8 PAD

Rig Name No:BASIC 1549/1549

Event: ABANDONMENT

Start Date: 4/16/2013

End Date: 5/13/2013

Spud Date: 7/31/1975

Active Datum: RKB @4,872.00usft (above Mean Sea Level)

UWI: SE/SW/0/3/N/66/W/8/0/0/6/0/S/300.00/0/0/0/0/0

Report No	Report Date	MD (usft)	24 Hr Summary
1	04/16/2013		MIRU Basic 1549. Kill well. ND well head. Studs were badly rusted. NU BOP. LD 1 1/2" tbg. SI. SDFN.
2	04/17/2013		RU Frontier & run gyro. RU Warrior & run 3.81" gauge ring Set CIBP @ 7760'. Dump bail 2 sks cmt on CIBP. Run CBL from 7506' to 6900'. Cmt top @ 7120'. SI. SDFN.
3	04/18/2013		PU 40 jts tbg. Air compressor on rig broke. Repair rig. Finish PU tbg. Tag CIBP. LD tag jt. RU Baker. Spot 40 sks G cmt w/20% Silica flour, .4% CD-32, .4% ASA=301, & .1% R-3. TOOH. SI. SDFN.
4	04/19/2013		RU Warrior. Shoot 3 - .62" holes @ 7000' & 6 - .62" holes @ 6500'. Set retainer @ 6512'. PU stinger & TIH. RU Baker. Squeeze w/130 sks G cmt. TOOH. RU Warrior. Shoot 3- .62" holes @ 5800' & 6 - .62" holes @ 4120'. Set retainer @ 4130'. PU stinger & TIH.
5	04/22/2013		RU Baker. Squeeze Sussex w/1000 sks G cmt w/.25 #/sk Celloflake. TOOH w/700' of tbg. LD remaining tbg. SI. SDFN.
6	04/23/2013		RU Warrior. Cut off csg @ 640'. Circ well. ND BOP. Pull csg slips. NU BOP to surface head. LD csg. TIH to 710'. RU Baker. Spot 175 sks Type III cmt w/2% CaCl2. LD tbg. ND BOP. RU Warrior. Tag cmt top @ 180. Set 8 5/8" CIBP @ 100'. Ttest to 1000 psi. OK.
7	05/13/2013		TIME : 1:00 PM, ROUTE : N33, WINS: 75790, PROJECT TYPE: P & A, BATT#: 34002496, GATHERER: KMG, STATION: O8341, LINE : 14-341-4, COMMENTS: P&A'D OFFLINE - WELLBORE IS PERMANENTLY ABANDONED
8	05/13/2013		Crew travel, safety. Dug up casing. Cut casing 6' below GL. Tagged @ 100'. Filled csg w 57 bags 5000# cement. Capped csg w plate containing well info. Backfilled.