

Name
SHIDELER 30-3A (O19EB)

**Actual
Conditions
(MD / TVD)**

Wasatch	Surface/	Surface
14.75" Hole to 190' MD		
12.25" Surface Hole		

Surface Casing	1123 / 1110
9-5/8" 11.6# J55 LTC	

Cemented to surface with

Lead: 271 sxs 12.5# G at 2.11 ft3/sk

Tail: 149 sxs 15.8# G at 1.18 ft3/sk

Total: 420 sxs

8.75" Hole to TD

TOC from CBL: 3060' MD

Ohio Creek (not picked)	
Mesaverde Marker	3626 / 3571
Williams Fork	4484 / 4416
Top Gas	5119 / 5043
Coal Ridge	6743 / 6665
Rollins	7428 / 7350
Cozzette	N/A / N/A
Corcoran	N/A / N/A
Actual TD	7854 / 7776

Production Casing 7824 / 7746

4.5" 11.6# S80 BTC

Cement with:

Lead: 472 sxs 12# TXI Lead at 1.79 ft3/sk

Tail: 467 sxs13# TXI Tail at 1.88 ft3/sk

Total: 939 sxs at 30% excess

(volume includes 30% excess)