

Name
SHIDELER 30-3B (O10EB)

**Actual
Conditions
(MD / TVD)**

16" Conductor @ 40'
Cement to surface with 5 yds redi-mix

Wasatch	Surface/	Surface
14.75" Hole to 210' MD		
12.25" Surface Hole		

Surface Casing	1131 / 1097
9-5/8" 36# J55 LTC	
Cemented to surface with	
Lead: 277 sxs 12.5# G at 2.11 ft3/sk	
Tail: 149 sxs 15.8# G at 1.18 ft3/sk	
Total: 426 sxs	

8.75" Hole to 6705' MD
7.875" Production Hole

TOC from CBL: 3500' MD

Ohio Creek (not picked)	
Mesaverde Marker	4196 / 3918
Williams Fork	4782 / 4465
Top Gas	5694 / 5344
Coal Ridge	7149 / 6796
Rollins	7849 / 7495
Cozzette	N/A / N/A
Corcoran	N/A / N/A
Actual TD	8340 / 7986

Production Casing	8287 / 7933
4.5" 11.6# S80 BTC	
Cement with:	
Lead: 480 sxs 12# TXI at 1.79 ft3/sk	
Tail: 381 sxs 13# TXI at 1.88 ft3/sk	
Total: 861 sxs	