

Catamount Energy Partners, Campbell #1, Section 4-T33N-R7W Permit

P&A Assesment for the CLARA OHNEMUS #1-4

BP America Plugged and Abandoned the captioned well.

They Plugged the Mesaverde Formation (5538-5768) on 10-1991 with a Bridge Plug and cement. They P&A'd the Fruitland formation and the well on 10/11/2011. They set a CIBP @ 3343' with 5 sacks of cement. They also set cement plugs at 2750-2800' (11 sks) & 0-550' (125 sks). This P&A was approved by Mark Weems, COGCC, on 5/21/2012. Catamount believes this well was plugged and Abandoned with best available engineering practices which eliminate any risk of nearby drilling or completion operations.