

WELLBORE DIAGRAM

Directions: Hwy 85 N to Hwy 392, W to WCR 21, N to WCR 78, 1/2 mi W, N to location

Bayswater Exploration & Prod

Lake 4-27

SESW Sec 22 T7N R67W

SHL: 225' FSL, 2409' FWL

BHL: 646' FNL, 646' FWL

Weld County CO

05-123-35687

Updated

02/25/13

JRR

G.L.= 5004

K.B.= 5020

16

8-5/8" 24# set at 755' (12-1/4" hole)
Cmt'd w/ 530 sx to Surf.

TOC: 1470'
CBL

<< >>

Nio A: 7348'-7368', 4 spf

8/28/12 Frac: 115,626 gals, 58,706 gals SLF, 33,000 lbs 30/50 White
CIFP 7415'

<< >>

Nio B: 7460'-7490', 4 spf

8/28/12 Frac: 221,849 gals, 168,691 gals SLF, 152,900 lbs 30/50 White
CIFP 7530'

<< >>

Nio "C": 7556'-7588', 4 spf

8/28/12 Frac: 209,065 gals, 131,461 gals SLF, 120,460 lbs 30/50 White
CIFP: 7620'

<< >>

CODL: 7664'-7683', 4 spf

8/17/12 Frac: 277,538 gals, 180,331 gals SLF, 180,180 lbs 30/50 White

PBTD= 7,791'

TD MD= 7,820'

TD VD= 7,434'

4-1/2" 11.6# CSG @ 7808' (7-7/8" O.H.)

Cmt'd w/ 1010 sx