

FORM  
2

Rev  
12/05

# State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400426750

Date Received:

## APPLICATION FOR PERMIT TO:

1.  Drill,  Deepen,  Re-enter,  Recomplete and Operate

### 2. TYPE OF WELL

OIL  GAS  COALBED  OTHER \_\_\_\_\_  
SINGLE ZONE  MULTIPLE  COMMINGLE

Refiling

Sidetrack

PluggingBond SuretyID

20090043

3. Name of Operator: SYNERGY RESOURCES CORPORATION

4. COGCC Operator Number: 10311

5. Address: 20203 HIGHWAY 60

City: PLATTEVILLE State: CO Zip: 80651

6. Contact Name: Brianne Visconti Phone: (970)737-1073 Fax: (970)737-1045

Email: bvisconti@syrginfo.com

7. Well Name: Kelly Farms Well Number: 22-4-3NHZ

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 12154

### WELL LOCATION INFORMATION

10. QtrQtr: SENW Sec: 4 Twp: 5N Rng: 66W Meridian: 6

Latitude: 40.431524 Longitude: -104.787390

Footage at Surface: 2130 feet FNL 2330 feet FWL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4753 13. County: WELD

### 14. GPS Data:

Date of Measurement: 02/22/2013 PDOP Reading: 1.4 Instrument Operator's Name: Aaron Demo

15. If well is  Directional  Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: 2353 FNL 2594 FEL 2180 FNL 2118 FWL  
Bottom Hole: 2180 FNL 2118 FWL  
Sec: 4 Twp: 5N Rng: 66W Sec: 3 Twp: 5N Rng: 66W

16. Is location in a high density area? (Rule 603b)?  Yes  No

17. Distance to the nearest building, public road, above ground utility or railroad: 242 ft

18. Distance to nearest property line: 226 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 330 ft

### 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		400	GWA

21. Mineral Ownership:  Fee  State  Federal  Indian Lease #: \_\_\_\_\_

22. Surface Ownership:  Fee  State  Federal  Indian

23. Is the Surface Owner also the Mineral Owner?  Yes  No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease?  Yes  No

23b. If 23 is No:  Surface Owners Agreement Attached or  \$25,000 Blanket Surface Bond  \$2,000 Surface Bond  \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

E/2 of the NW/4 Section of 4, NE/4 of Section 4, NW/4 of Section 3, 5N, 66W - Wellbore crosses lease lines within drilling and spacing unit; distance to nearest lease line is 0 feet; distance to Unit boundary is greater than 460'.

25. Distance to Nearest Mineral Lease Line: 0 ft 26. Total Acres in Lease: 400

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated?  Yes  No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling?  Yes  No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling?  Yes  No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)?  Yes  No

31. Mud disposal:  Offsite  Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method:  Land Farming  Land Spreading  Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	1,200	660	1,200	0
1ST	8+3/4	7	26	0	7,482	125	7,482	
1ST LINER	6+1/8	4+1/2	13.5	6357	12,154			

32. BOP Equipment Type:  Annular Preventer  Double Ram  Rotating Head  None

33. Comments o Conductor casing will not be used. o Operator request an exception location per rule 318 A.a. Request letter and waiver are attached. o Operator requests the proposed spacing unit: 320 Acres, E/2 of the NW/4 Section of 4, NE/4 of Section 4, NW/4 of Section 3, 5N, 66W.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ?  Yes  No

36. Is this application part of submitted Oil and Gas Location Assessment ?  Yes  No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Craig Rasmuson

Title: VP Operations Date: \_\_\_\_\_ Email: crasmuson@syrinfo.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

API NUMBER

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

**CONDITIONS OF APPROVAL, IF ANY:**

**All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.**

Data retrieval failed for the subreport 'IntPolicy\_NTC' located at: \\lnetpub\NetReports\policy\_ntc.rdl. Please check th

### Attachment Check List

Att Doc Num	Name
400426760	DIRECTIONAL DATA
400426761	PROPOSED SPACING UNIT
400426763	PLAT
400426764	DEVIATED DRILLING PLAN
400426766	OFFSET WELL EVALUATION
400426768	EXCEPTION LOC REQUEST
400426770	EXCEPTION LOC WAIVERS
400427883	EXCEPTION LOC WAIVERS
400427885	EXCEPTION LOC REQUEST

Total Attach: 9 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

### BMP

<u>Type</u>	<u>Comment</u>
Drilling/Completion Operations	Anti-collision: Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as-constructed gyro survey will be submitted to COGCC with the Form 5.
Drilling/Completion Operations	Operator will comply with COGCC Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.

Total: 2 comment(s)