

FORM
5
Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:
400428375

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type Final completion Preliminary completion

1. OGCC Operator Number: 100322
2. Name of Operator: NOBLE ENERGY INC
3. Address: 1625 BROADWAY STE 2200
City: DENVER State: CO Zip: 80202
4. Contact Name: Kathleen Mills
Phone: (720) 587-2226
Fax: (303) 228-4286

5. API Number 05-123-35545-00
6. County: WELD
7. Well Name: Shelton PC Well Number: G25-74-1HN
8. Location: QtrQtr: NWNE Section: 25 Township: 4N Range: 65W Meridian: 6
Footage at surface: Distance: 285 feet Direction: FNL Distance: 2381 feet Direction: FEL
As Drilled Latitude: 40.289690 As Drilled Longitude: -104.610800

GPS Data:
Date of Measurement: 01/09/2013 PDOP Reading: 2.0 GPS Instrument Operator's Name: PAUL TAPPY

** If directional footage at Top of Prod. Zone Dist.: 802 feet. Direction: FNL Dist.: 1641 feet. Direction: FEL
Sec: 25 Twp: 4N Rng: 65W
** If directional footage at Bottom Hole Dist.: 548 feet. Direction: FSL Dist.: 1615 feet. Direction: FEL
Sec: 25 Twp: 4N Rng: 65W

9. Field Name: WATTENBERG 10. Field Number: 90750
11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 12/04/2012 13. Date TD: 12/11/2012 14. Date Casing Set or D&A: 12/12/2012

15. Well Classification:
 Dry Oil Gas/Coalbed Disposal Stratigraphic Enhanced Recovery Storage Observation

16. Total Depth MD 11438 TVD** 6946 17 Plug Back Total Depth MD 11333 TVD** 6841

18. Elevations GR 4795 KB 4825
One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:
CBL, MUD, GR

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	24	16	75	0	130				
SURF	13+3/4	9+5/8	36	0	653	314	0	653	VISU
1ST	8+3/4	7	26	0	7,433	600	1,304	7,433	CALC
1ST LINER	6+1/8	4+1/2	11.6	7219	11,334	0			

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PIERRE	2,696		<input type="checkbox"/>	<input type="checkbox"/>	
PARKMAN	3,866		<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	4,495		<input type="checkbox"/>	<input type="checkbox"/>	
SHANNON	5,109		<input type="checkbox"/>	<input type="checkbox"/>	
TEEPEE BUTTES	6,217		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,057		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Kathleen Mills

Title: Regulatory Analyst Date: _____ Email: kmills@nobleenergyinc.com

Attachment Check List

Att Doc Num	Document Name	attached ?	
Attachment Checklist			
400428384	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400428385	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
Other Attachments			
400428383	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400428386	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

User Group

Comment

Comment Date

User Group	Comment	Comment Date

Total: 0 comment(s)