

FORM
5A

Rev
06/12

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400428786

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 96850
2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC
3. Address: 1001 17TH STREET - SUITE #1200
City: DENVER State: CO Zip: 80202
4. Contact Name: Sandra Salazar
Phone: (303) 629-8456
Fax: (303) 629-8268

5. API Number 05-045-21550-00
6. County: GARFIELD
7. Well Name: Hoeppli
Well Number: RWF 532-36
8. Location: QtrQtr: SWNE Section: 36 Township: 6S Range: 94W Meridian: 6
9. Field Name: RULISON Field Code: 75400

Completed Interval

FORMATION: WILLIAMS FORK - CAMEO Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 04/27/2013 End Date: 05/01/2013 Date of First Production this formation: 05/01/2013

Perforations Top: 6292 Bottom: 8698 No. Holes: 152 Hole size: 35/100

Provide a brief summary of the formation treatment: Open Hole: ☐

2445 Gals 7 1/2% HCL; 1122300 # 40/70 Sand; 30913 Bbls Slickwater (Summary)

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 30972 Max pressure during treatment (psi): 6622

Total gas used in treatment (mcf): Fluid density at initial fracture (lbs/gal): 8.43

Type of gas used in treatment: Min frac gradient (psi/ft): 0.67

Total acid used in treatment (bbl): 58 Number of staged intervals: 7

Recycled water used in treatment (bbl): 30913 Flowback volume recovered (bbl): 7975

Fresh water used in treatment (bbl): Disposition method for flowback: RECYCLE

Total proppant used (lbs): 1122300 Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 05/28/2013 Hours: 24 Bbl oil: 0 Mcf Gas: 715 Bbl H2O: 0

Calculated 24 hour rate: Bbl oil: 0 Mcf Gas: 715 Bbl H2O: 0 GOR: 0

Test Method: Flowing Casing PSI: 1387 Tubing PSI: 935 Choke Size: 14/64

Gas Disposition: SOLD Gas Type: DRY Btu Gas: 1025 API Gravity Oil: 0

Tubing Size: 2 + 3/8 Tubing Setting Depth: 8438 Tbg setting date: 05/04/2013 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

- All flowback water entries are total estimates based on commingled volumes.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Sandra Salazar

Title: Permit Technician II Date: _____ Email sandra.salazar@wpenergy.com
:

Attachment Check List

Att Doc Num	Name
400428823	WELLBORE DIAGRAM

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)