

FORM  
5Rev  
02/08

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400429923

Date Received:

## DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 100322

4. Contact Name: Julie Webb

2. Name of Operator: NOBLE ENERGY INC

Phone: (720) 587-2316

3. Address: 1625 BROADWAY STE 2200

Fax:

City: DENVER State: CO Zip: 80202

5. API Number 05-123-22744-00

6. County: WELD

7. Well Name: DUNBAR

Well Number: 18-31

8. Location: QtrQtr: NESW Section: 18 Township: 6N Range: 66W Meridian: 6

Footage at surface: Distance: 1770 feet Direction: FSL Distance: 2183 feet Direction: FWL

As Drilled Latitude: As Drilled Longitude:

## GPS Data:

Date of Measurement: PDOP Reading: GPS Instrument Operator's Name:

\*\* If directional footage at Top of Prod. Zone Dist.: feet. Direction: Dist.: feet. Direction:

Sec: Twp: Rng:

\*\* If directional footage at Bottom Hole Dist.: feet. Direction: Dist.: feet. Direction:

Sec: Twp: Rng:

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 03/31/2005 13. Date TD: 04/03/2005 14. Date Casing Set or D&amp;A: 04/05/2005

## 15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7354 TVD\*\* 17 Plug Back Total Depth MD 7332 TVD\*\*

18. Elevations GR 4827 KB 4839

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

## 19. List Electric Logs Run:

Gamma Ray CCL/CBL

## 20. Casing, Liner and Cement:

## CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24	0	838	580	0	838	CALC
1ST	7+7/8	4+1/2	11.6	0	7,347	395	3,906	7,354	CBL

## STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: 12/19/2012

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom
	S.C. 1.1		100	3,342	3,613

## Details of work:

Control well w/ kill fluid. RIH w/ blade bit, and scraper, 220 jts. Tagged fill at 6912' KB. TIH w/ RBP, retrieved head, 217 jts 2 3/8" tubing. Set RBP @ 6800' KB w/ 217 jts. Pressure test to 2000#. Roll hole. Spot sand on plug. Unland casing. Pick Up mule shoe and TIH w/229 jts of 1 1/4" to 3175'. Test lines to 3000 psi. Pump 100 sks of "G" neat 15.8 ppg cement from 3613' to 3342'. Reland casing. Bond log from 4000' to surface. RIH w/ retrieving head and establish circulation and latch onto RBP. Roll hole clean and release RBP. Land 2 3/8" 4.7 # J-55 tubing to 7185' KB. Rig down and move off.

## 21. Formation log intervals and test zones:

**FORMATION LOG INTERVALS AND TEST ZONES**

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
			<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Julie Webb

Title: Regulatory Analyst Date: \_\_\_\_\_ Email: juliewebb@nobleenergyinc.com

**Attachment Check List**

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400429938	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Directional Survey **	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400429940	PDF-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

**General Comments**

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)