

FORM
5

Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400429157

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 100322

4. Contact Name: Kathleen Mills

2. Name of Operator: NOBLE ENERGY INC

Phone: (720) 587-2226

3. Address: 1625 BROADWAY STE 2200

Fax: (303) 228-4286

City: DENVER State: CO Zip: 80202

5. API Number 05-123-36042-00

6. County: WELD

7. Well Name: Wells Ranch State USX

Well Number: AA16-67-1HNL

8. Location: QtrQtr: SWNW Section: 14 Township: 6N Range: 63W Meridian: 6

Footage at surface: Distance: 1855 feet Direction: FNL Distance: 238 feet Direction: FWL

As Drilled Latitude: 40.488788 As Drilled Longitude: -104.412580

GPS Data:

Data of Measurement: 11/14/2012 PDOP Reading: 4.9 GPS Instrument Operator's Name: PAUL TAPPY

** If directional footage at Top of Prod. Zone Dist.: 1676 feet. Direction: FNL Dist.: 927 feet. Direction: FEL

Sec: 15 Twp: 6N Rng: 63W

** If directional footage at Bottom Hole Dist.: 1743 feet. Direction: FNL Dist.: 649 feet. Direction: FWL

Sec: 16 Twp: 6N Rng: 63W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 12/06/2012 13. Date TD: 12/14/2012 14. Date Casing Set or D&A: 12/18/2012

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 16215 TVD** 6715 17 Plug Back Total Depth MD 16199 TVD** 6699

18. Elevations GR 4778 KB 4802

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL, MUD, GR

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	24	16	42.09	0	124	80	0	124	VISU
SURF	13+3/4	9+5/8	36	0	674	385	0	674	VISU
1ST	8+3/4	7	26	0	7,101	565	1,250	7,101	CALC
1ST LINER	6+1/8	4+1/2	11.6	6942	16,200	0			

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PIERRE	2,884		<input type="checkbox"/>	<input type="checkbox"/>	
PARKMAN	3,600		<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	4,361		<input type="checkbox"/>	<input type="checkbox"/>	
SHANNON	4,918		<input type="checkbox"/>	<input type="checkbox"/>	
TEEPEE BUTTES	5,943		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	6,648		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Kathleen Mills

Title: Regulatory Analyst Date: _____ Email: kmills@nobleenergyinc.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400429193	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400429194	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400429195	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400430852	PDF-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400430853	PDF-GAMMA RAY	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400430854	PDF-GAMMA RAY	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400430855	LAS-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400430857	PDF-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400430858	PDF-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400430859	LAS-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)